

[Ownership Matrix](#)[Click for copy of Word \(native\) file](#)**TABLE OF CONTENTS**

1.0	PURPOSE AND SCOPE	3
2.0	IMPLEMENTATION	3
3.0	STANDARD	3
3.1	Control of Original CAD Data Sets and Manual Drawings.....	3
3.2	Drawing Categories	3
3.3	Computer-Aided Drafting.....	4
3.4	Drawing Sizes	9
3.5	Drawing Material	9
3.6	Drawing Arrangement	9
3.7	Title Block	11
3.8	References Block	15
3.9	Next Used On Documentation	16
3.10	Drawing Traceability List.....	16
3.11	General Notes	17
3.12	Drawing Status Area.....	17
3.13	Parts/Material List.....	17
3.14	General Practice	17
3.15	Abbreviations and Acronyms	17
3.16	Symbology	17
3.17	Legibility.....	18
3.18	Drawing List	18
3.19	Lettering.....	19
3.20	Drawing Orientation	19
3.21	Coordinate System and Geodetic Elevation Data	19
3.22	Parts/Material List.....	19
3.23	Component Numbering.....	23
3.24	Measurement System.....	23
3.25	Revisions.....	24
3.26	Official Use Only and Export Controlled Drawings.....	27
3.27	Superseded Drawings, Voided Drawings, and Title Block Changes	27
3.28	Changing the Title of a Drawing	28
3.29	Interface Control	28
4.0	DEFINITIONS	28
5.0	SOURCES.....	30
5.1	Requirements	30
5.2	References.....	30

TABLE OF FIGURES

Figure 1.	Layer Naming Standard.....	5
Figure 2.	Discipline Identifiers.	6
Figure 3.	Layer-Use Identifiers.....	6
Figure 4.	Plotter Pen Assignments.....	8
Figure 5.	Block Locations and Drawing Arrangement	10
Figure 6.	Typical Title Block.....	11
Figure 7.	Alternate Title Block.....	11

Figure 8. Title Block with Supplemental Block for Project Identification.	12
Figure 9. Areas Represented by Drawing Prefixes.	15
Figure 10. Typical Reference Block.	16
Figure 11. Drawing Traceability List.....	16
Figure 12. Drawing Types and Classifications.	20
Figure 13. Parts/Materials List Placement.	21
Figure 14. International Projection Symbol.	24
Figure 15. Typical Revision Block.	24
Figure 16. CADCODE and CADFILE Strikeout.....	26

TABLE OF ATTACHMENTS

ATTACHMENT A – GUIDE TO HISTORICAL DRAWING NUMBERS	32
ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY DISCIPLINE	33
ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,	44
ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,	63
ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS	76
ATTACHMENT F – PARTS/MATERIALS LIST	90

1.0 PURPOSE AND SCOPE

(5.1.2)

This standard establishes Tank Operations Contractor (TOC) requirements, conventions, and practices (standards) for preparing and revising engineering drawings entered into the Hanford Document Control System. These standards apply to engineering drawings prepared by and for the TOC that depict facilities, systems and components. (5.1.1, 5.1.3)

2.0 IMPLEMENTATION

This procedure is effective on the date shown in the header.

NOTE: Deviations to any requirements of this standard shall be requested from the standard document owner. Approved deviations shall be documented in the accompanying Standard Basis Document (e.g., RPP document). A Standard Basis Document shall be established prior to approval of any new deviations.

3.0 STANDARD

3.1 Control of Original CAD Data Sets and Manual Drawings

The TOC Central Design Authority & Standards organization manages access to the original computer-aided design (CAD) data sets. Central Design Authority & Standards identifies the custodians who have editing (revision) access to the original data sets. The Information Resource Management (IRM) Service Provider stores the original CAD data sets and hard copy drawings (tracings), and ensures that only authorized personnel are given access. Approved engineering drawings are transferred to the IRM Service Provider for microfilming and storage in accordance with [TFC-ENG-DESIGN-C-09](#).

3.2 Drawing Categories

3.2.1 General

This standard applies to the engineering drawings that represent the technical information for the structures, systems, and components (SSC) required by the TOC. Drawings are identified by the “H-series” or “SK-series” drawing categories. The H-series drawings are for permanent facility SSC and usually include the drawings associated with modification, design, construction, and fabrication activities. The SK-series drawings involve temporary SSC that usually include the drawings for conceptual design, interface control, and equipment with a limited life. See Attachment A for historical drawing numbering system guidance.

3.2.2 H-Series Drawings

These drawings are permanent records and are subject to as-built requirements once field work is complete. The H-series drawings numbers are obtained from the Hanford Document Numbering System (HDNS). The H-series drawings include several different drawing types, such as arrangement, assembly, detail, schematic, wiring diagram, block diagram, flow diagram, installation, layout, plot plan, piping and instrumentation diagram (P&ID), and altered-item drawings. This list is not all-inclusive, and other types of drawings may be necessary for particular purposes. (5.1.4)

3.2.3 SK-Series Drawings

These drawings are prepared as temporary drawings for SSCs that will not become part of the permanent facility. The SK-series drawing numbers are obtained from HDNS. These drawings are record information and are subject to the same control requirements as H-series drawings.

Examples of SK-series drawings:

- Experimental/prototypical equipment
- Limited-use test equipment
- Conceptual designs
- Interface control
- Temporary equipment supporting operations (usually in-service for less than two years).

If the depicted information (i.e., all or part) on an SK-series drawing is determined to be needed as part of the permanent facility SSC, then that information is integrated into the drawing baseline by one of the following methods:

1. Complete Drawing Transfer - Convert the SK-series drawing to a new H-series drawing by obtaining an entirely new drawing number from HDNS to replace the SK-series drawing number. If the converted SK-series drawing is being added as a new sheet(s) to an existing H-series drawing, then the new drawing sheet number is obtained from HDNS. Provide two-way traceability between the newly created H-series drawing and the SK-series drawing. Supersede the SK-series drawing through the ECN process.
2. Partial Drawing Transfer - Integrated the needed portion of SSC details from the SK-series drawing on to the affected H-series drawing through a drawing revision. Identify the two-way traceability between the affected H-series drawing and the SK-series drawing. Supersede the remaining portion of the SK-series drawing through the ECN process.

3.2.4 Vendor Drawings

Vendor-supplied drawings are submitted to the IRM Service Provider in accordance with TFC-BSM-IRM_DC-C-07.

An altered-item drawing (see definition in Section 4.0) must be developed for vendor items that require modification as part of a design, or modification to items covered by a vendor item file. See Section 3.22.10.

3.3 Computer-Aided Drafting

3.3.1 CAD Program

AutoCAD Release 16 (AutoCAD 2005) or earlier versions is the standard for preparing all engineering drawings that will be released into the Hanford Document Control System. Drawings developed on CAD programs other than AutoCAD¹ must be converted to the standard AutoCAD program “.DWG” format prior to releasing the data files to the IRM contractor. Generate final plots from the “.DWG” formatted file.

¹ Registered trademark of Autodesk.

3.3.2 AutoCAD Discipline Layering Standards

Uniform layering standards are established to make it easier to exchange AutoCAD data sets among organizations and companies. Consistency allows logical separation and identification of drawing data, and permits the user to view and plot related aspects of a drawing separately or in combination.

3.3.2.1 Layering

Designating layers by color and line type is the preferred standard. Layers can also be assigned on an entity basis. This section and Attachment B describe the standards to be used when assigning layers.

Drawing setup files (also identified in AutoCAD documentation as “prototype drawings”) establish specific discipline layers for routine use. Attachment B, Tables 1 through 9, covers the following:

- Table B-1, General Layering for All Disciplines
- Table B-2, Architectural Drawings
- Table B-3, Civil/Structural/Environmental Drawings
- Table B-4, Electrical Drawings
- Table B-5, Fire Protection Drawings
- Table B-6, HVAC Drawings
- Table B-7, Instrumentation & Control (I&C) Drawings
- Table B-8, Mechanical Drawings
- Table B-9, Piping Drawings.


For mapping and mapping related drawings, use the computer automated mapping and information system (CAMIS) layering standards.

Third-party software approved for use by the TOC, with built-in layering standards, is exempt from this layering standard requirement. However, to support third-party software, a special plotter configuration may be required.

3.3.2.2 Layer Naming Standard

Figure 1 shows the layer-naming standard that is to be used on AutoCAD-developed drawings.

Figure 1. Layer Naming Standard.



3.3.2.3 Discipline Identifier

This identifier defines the specific engineering discipline. A unique identifier enables users to quickly distinguish discipline layers within a drawing file and provides a logical separation of discipline information, as defined by Figure 2 (also see Figure 1).

Figure 2. Discipline Identifiers.

Identifier	Discipline	Identifier	Discipline
A	Architectural	H	HVAC
C	Civil	I	Control Systems
E	Electrical	N	Mechanical/Machine
F	Fire Protection	P	Piping
G	General (non-specific applications)	S	Structural

3.3.2.4 Layer-Use Identifier

The layer-use identifier designates what the layer depicts (e.g., primary objects, existing equipment, hidden objects, or text). The layer-use identifier is used only when a single line type and color is assigned to an individual layer as defined by Figure 3 (also see Figure 1). Normally, this identifier is not used for entity-based layers.

Figure 3. Layer-Use Identifiers.

Identifier	Layer-Use	Line Type
O	New or main object, visible lines, primary line work	Continuous
E	Existing equipment - For A-E use to depict existing facility/ equipment	Phantom
F	Future items - For A-E use to depict future items	Dashed
D	Demolition - For A-E use to depict demolition information	Dashed
T	Test	Continuous
M	Dimensioning (in accordance with ASME Y14.5M)	Continuous
C	Center Lines	Center
H	Hidden items/lines	Hidden
X	Hatching	Continuous
P	Mechanical details depicting repeated details (e.g., spring and screw thread details or alternate positioning of absent parts)	Phantom
R	Reused equipment – For A-E use to depict Reused facility/equipment	Continuous
V	Viewing and Cutting Planes	Varies

NOTE: Selecting the Polyline feature will limit the minimum Polyline width to the plotter line width that is established by the line color.

Certain conditions may make it desirable to link layer data together but still keep the data separate. For example, if a piping modification required new equipment to be installed after the old equipment is removed, the layer-use identifier could be used to separate data as follows:

- Add auxiliary details, as needed. Example: 3DET
- PE-PIPING - Existing piping
- PD-PIPING - Piping to be removed (demolition)
- PO-PIPING - New piping to be installed
- PF-PIPING - Piping to be considered for future installation.

3.3.2.5 Object/Function Identifier

The object/function identifier provides a semi-descriptive name of layer contents or function. The identifier may be as many as 28 characters in length and may contain letters, numerals, and special characters, such as \$ (dollar), - (hyphen), and _ (underscore). (See Figure 1 and Attachment B, Tables B-1 through B-9.)

When words used in the object/function identifier are abbreviated, use of the latest edition of American Society of Mechanical Engineers (ASME) Y14.38, “Abbreviations and Acronyms,” is the preferred standard.

3.3.2.6 Plotter Pen Assignments

Plotters are configured to produce line widths based on colors. Designating specific AutoCAD colors to the plotter pens does this. This allows specific line weights to be generated by the plotter and minimizes the need to use AutoCAD Polylines for all line work within a drawing.

Care should be taken to ensure that the selected color/line weight will produce the desired line width on the final drawing plot. The line type and color should provide the optimum contrast with the visible/object line width on the drawing. See Figure 4 for available plotter line widths.

3.3.2.7 New-Drawing Setup Files

New-drawing setup files, also identified in AutoCAD documentation as Prototype drawings, are pre-configured by means of this layering convention. (See Attachment B, Tables B-1 through B-9.)

The startup files are not all-inclusive of required layers. Additional layers may be created, as needed, to provide for specific drawing needs. The specified naming standard described here is to be used to develop additional layers.

Figure 4. Plotter Pen Assignments.

Pen No. 1 0.25mm (0010in.)	Pen No. 2 0.35mm (0.014in.)	Pen No. 3 0.5mm (0.020in.)	Pen No. 4 0.7mm (0.028in.)	Pen No. 5 0.95mm (0.038in.)
Color Assignment	Color Assignment	Color Assignment	Color Assignment	Color Assignment
Primary Color	Primary Colors	Primary Color	Primary Colors	Primary Color
8 (8)	5 (Blue) 6 (Magenta) 7 (White)	4 (Cyan)	2 (Yellow) 3 (Green)	1 (Red)
Optional Colors	Optional Colors	Optional Colors	Optional Colors	Optional Colors
X3 (e.g., 13, 53, 123, 243)	X2 (e.g., 12, 22, 32, 152, 222) 252-75% screen	X1 (e.g., 11, 71, 181, 241)	X0 (e.g., 10, 90, 100, 230) X5, X6, X7, X8, X9	X4 (e.g., 14, 64, 134, 214)

3.3.2.8 Layering Modification

Anyone may request additions or revisions to the Hanford Site discipline-layering standard. A request for changes must be submitted to Central Design Authority & Standards in writing. The request must provide justification and specific changes.

3.3.3 X-Reference Files

Prior to submitting files to the IRM Service Provider, X-Reference (see definition in Section 4.0) files must be bound to the AutoCAD “.DWG” drawing file.

3.3.4 Manual Modification or Revision of CAD-Generated Drawings

When a drawing is released, the CAD data set must reflect the released drawing. If a CAD-generated plotted drawing is changed (e.g., field of the drawing is changed) before it is issued, then the CAD data set must be updated to reflect the changes before issuing the drawing to the IRM contractor for release.

All manual changes are to be initialed and dated by the person making the changes. The engineer adds, signs, and dates a note stating that the manual changes to the drawing have been incorporated into the CAD data set. The note is placed above the Title Block on the drawing.

Engineering Change Notices incorporated into a released drawing that requires a manual change or alteration as a result of lost or corrupted CAD data sets, where the data set cannot be corrected, must have a note added to the drawing stating that the drawing is a manual drawing. Place the words “MANUAL DRAWING” above the title block in 1/2” high lettering. This signifies that the drawing has been manually updated and that the data set is not available for updating.

3.3.5 Third-Party CAD Software

Third-party software used in the development of AutoCAD-based drawings must be the type that does not require access to the third-party software to revise the drawings.

3.3.6 Shape Files and Non-Standard Fonts

Data sets of released engineering drawings are not to use nonstandard shape files and fonts (i.e., font files not supplied by AutoCAD) (see Section 3.19).

3.3.7 CAD Auxiliary Support Files/Information

Auxiliary support files/information is available on request from Central Design Authority & Standards. The available files and information include:

- Drawing start models (AutoCAD prototype drawings)
- Drawing Title Block formats
- Symbol libraries (see section 3.16) (e.g., architectural, electrical, control systems; heating, ventilation, and air conditioning [HVAC]; and P&ID).

3.4 Drawing Sizes

Drawings are sized in accordance with ASME Y14.1, “Decimal Inch Drawing Sheet Size and Format.”

The ASME “F” size drawing (28” x 40”) is the preferred inch size. Use of the International Standards Organization (ISO) standard paper sizes is optional. The ISO “A1” size drawing (594 mm x 841 mm) is the preferred metric size. The ANSI “E” size, ISO “A0” size, and roll or elongated size drawings may be used with the authorization of Central Design Authority & Standards.

3.5 Drawing Material


CAD drawings are plotted on bond paper that is a minimum of 20 lb. opaque paper.

3.6 Drawing Arrangement

The general drawing arrangement must conform to ASME Y14.1, except for the location of the parts/materials list and the REVISIONS Block (see Figure 5). Configure drawing arrangement as shown in Figure 5 and as defined in this standard.

Figure 5. Block Locations and Drawing Arrangement.

The CADFILE and CADCODE shown on older title blocks are no longer required and are to be left blank on new drawings that enter the drawing system for initial release. See also Section 3.25.4.3.



3.7.5 Index Number

The Drawing Index System uses numerical digits to categorize TOC drawings for storage and retrieval purposes. An index number is required on each drawing. The number is shown in the INDEX NO Block of each drawing.

Index numbers are listed in Attachment C, “Index Number System for Engineering Drawings, Alphabetic Listing” and Attachment D, “Index Number System for Engineering Drawings, Numeric Listing.” An index number is assigned for each major category covered by the drawing. Non-essential numbers are not shown (e.g., 0801 and 0802 are not shown along with 0800 on a single drawing).

Off-site A-Es obtain index numbers from the designated TOC point of contact.

3.7.5.1 Index System

The complete index number comprises four or six numerical digits. The first two digits identify the primary subject (i.e., 00 to 99). The next two digits identify the sub-category or secondary information (i.e., 01 to 99). The last two digits cover a further breakdown, if needed, of the information or tertiary subject (i.e., 01 to 99). An index number will have a minimum of four digits (e.g., 0804, Architectural Equipment Locations), or if the subject requires a further breakdown, the index number may require six digits (e.g., 590315, Control Systems, Wiring Diagrams, Safety Circuits).

3.7.5.2 Primary Subjects


Index Number	Subject
00	- Listing or Index
01 through 07	- Civil
08 through 14	- Architectural and Structural
15 through 58	- Mechanical
59 through 64	- Instrumentation
65	- Electronics
70	- Flow Diagrams
71 through 81	- Electrical
82	- Insulation and Heat Tracing
83	- Future
84 through 88	- Piping
89	- Heating, Ventilating, and Exhaust
90	- Air Conditioning Systems
91 through 98	- Future
99	- Miscellaneous Equipment not Identifiable or Related to Assembled Equipment

3.7.5.3 Secondary Subjects

The primary subjects are divided further into details or secondary subjects (e.g., 0804, Architectural Equipment Locations, or 7005, Piping and Instrument Diagram Closed Loop System (CLS). The 04 and 05 digits are added to denote the details).

3.7.5.4 Tertiary Subjects

The tertiary subjects, containing two digits, are used only in conjunction with the primary subjects and secondary subjects, 49, 50, 59, 60, and 85, to indicate the type of drawing. The complete six-digit index number for a drawing showing a wiring diagram for safety circuits would be:



The number is written as 590315.

3.7.5.5 Multiple Index Numbers

In some instances a drawing may contain two or more index categories (e.g., Cranes [3900] and Electrical Power Plans [7301]). In this instance, place both index numbers in the Title Block. If additional space is required, the index numbers are listed above the Title Block in the Drawing Status area of the drawing. Place a notation in the INDEX NO block referencing the drawing zone location of the list of index numbers (e.g., SEE ZONE A1; SEE ZN 1A).

3.7.6 Drawing Number

The drawing number is 0.24” to 0.35” high. Obtain drawing numbers from HDNS. The Hanford site area that the drawing represents must be provided to obtain drawing numbers. Drawing numbers are assigned in accordance with the Hanford Site area that the drawing represents. The drawing prefix series and the representative areas are listed in Figure 9.

For historical drawing number information, see also Attachment A, “Guide for Historical Drawing Numbers.”

3.7.7 Revision Number

Numeric revision numbers are used. The current revision number is noted in the Title Block in the REV block (see Figures 6, 7, and 16). Zero is normally used for the initial release; also see Section 3.25.

3.7.8 Scale

Enter the predominant scale of the drawing, or “NONE” when no scale is used.

3.7.9 Sheet Number

For single sheet drawings, a “1” is entered in the SHEET block. For multiple-sheet drawings, the sheets are in sequence starting with 1. Enter the total number of sheets on sheet 1 only. Each subsequent sheet shows only the next sequential sheet number.

3.7.10 Drawn By

Print the initials and surname of the originator.

3.7.11 Approval Signatures

Approvals are in accordance with [TFC-ENG-DESIGN-C-09](#). Preprinted or printed names with signatures placed next to or above the preprinted or printed names are required, and the signature must be legible.

Figure 9. Areas Represented by Drawing Prefixes.


Drawing Prefix	Area
H-1	100 Area
H-2	200 Area
H-3	300 Area
H-4	400 Area; Fast Flux Test Facility (FFTF)
H-5	Unassigned except for electrical drawings not specifically applicable to other areas
H-6	General area, not included in other defined areas, usually civil drawings and maps
H-7	700 Area and City of Richland (RCHN, RCHC, and RCHS)
H-8	800 Area, Exploratory Shaft Site
H-9	Specification Control Drawings
H-10	Not Used
H-11	1100 Area
H-12	3000 Area
H-13	General mapping of the Hanford Site; Environmental Permitting
H-14	Waste Tank Farm (200 East, 200 West, transfer lines, and associated electrical and instrumentation)

3.8 References Block

3.8.1 Construction or Detailed Design

Only the reference documents required by the construction contractors are listed (see Figure 10). New drawings depicting new construction or detailed design are not required to be listed in the REFERENCES block, but are shown on the drawing. List the Vendor Information File number of supplied/existing equipment as a reference. National consensus standards are not listed in the REFERENCES block.

Figure 10. Typical Reference Block.



3.8.2 Reference Document Number and Title

The reference document number is entered in the REF NUMBER block (see Figure 10). The actual title is entered in the TITLE block and may be abbreviated.


3.9 Next Used On Documentation

The NEXT USED ON block (see Figure 10) is used to document drawings that are linked together (e.g., a subassembly, detail and installation drawings). Link these drawings by referencing the next higher level or generation (e.g., a subassembly drawing will list the drawing number of the assembly or the installation drawing). If the drawing is the top drawing, the words "END ITEM" are entered.

3.10 Drawing Traceability List

The DRAWING TRACEABILITY LIST block itemizes the existing drawings affected by changes in design (see Figure 11). Show all affected drawings. The drawings are not to be duplicated in the REFERENCES block. All drawings are required to provide two-way traceability. Two-way traceability is cross-referencing existing engineering drawings affected by a new design or modification and vice versa.

Figure 11. Drawing Traceability List.



3.11 General Notes

The preferred location of the general notes is above the Title Block. Other locations may be used when additional space is required. On multiple-sheet drawings, General Notes start on sheet 1 and may continue on subsequent sheets.

3.12 Drawing Status Area

Reserve a space approximately 3" high above the Title Block on the drawing for recording additional Title Block information and for the application of A-E stamps according to individual contractor procedures.

3.13 Parts/Material List

The Parts/Material List is located, or begins, in the upper right-hand corner on the first sheet of the drawing. For additional parts/material list requirements, see section 3.22.

3.14 General Practice

Drafting is done according to applicable ASME Y14-series standards. Dimensioning and tolerancing is done according to ASME Y14.5M.

3.15 Abbreviations and Acronyms

3.15.1 Abbreviations

Abbreviations should conform to the latest edition of ASME Y14.38, "Abbreviations and Acronyms." Abbreviations on a drawing are used only when space does not permit the word(s) to be spelled out, such as in the drawing title, parts list, or a reference drawing list. Industry-accepted abbreviations, such as DIA, SCH, and REF are to be used to the fullest extent. The face of the drawing should be planned and drafted to provide ample space so that abbreviations can be held to a minimum, for clarity and interpretation.

Punctuation marks, except the slant (/) and the hyphen (-), are not to be used when abbreviations are used on drawings. A period (.) is added to an abbreviation only if in its context does not obviously represent an abbreviation (e.g., ADD indicates addition or addendum). Duplicate abbreviations are specified in the latest edition of ASME Y14.38. Before such abbreviations are used, care should be exercised to ensure that the proper meaning will be correctly interpreted.

3.15.2 Acronyms

Acronyms should conform to the latest edition of ASME Y14.38. Other acronyms should be avoided. However, if repeated use of a word in text (e.g., General Notes) makes the use of an acronym an obvious advantage, the acronym may be created. Hanford site-specific acronyms should be clearly defined by spelling out the acronym in the LEGEND or by using a general note. Hanford-specific acronyms are available at: <http://www.hanford.gov/acronym/>.

3.16 Symbology

Symbology used on drawings that defines components needs to be traceable to an engineering drawing (see section 3.16.1) or a LEGEND placed on the drawing. If additional symbology is required, which is not covered by the mandatory symbology listed below, industry accepted

standards will be used to the fullest extent possible with the symbology placed in a LEGEND on the drawing.

For additions or modifications of Hanford symbology, see section 3.16.3.

3.16.1 Mandatory Symbology

The uniform drawing symbology for the TOC is specified on H-14-020000, sheet 4.

3.16.2 Optional Symbology

The symbology specified by the following drawings is optional. It is provided as a drafting aid to increase efficiency in producing drawings. The symbology shown is preferred, but not mandatory.

- H-6-14982 Hanford Standard, General Symbology
- H-6-14983 Hanford Standard, Civil Symbology
- H-6-14984 Hanford Standard, Structural Symbology
- H-6-14985 Hanford Standard, Architectural Symbology
- H-6-14986 Hanford Standard, Machine Symbology.

3.16.3 Creation or Modification of Symbology Drawings

Additions or changes to the drawing symbols contained on drawing H-14-020000 are made in accordance with the ECN process.

3.16.3.1 AutoCAD Symbol Naming Standards

All AutoCAD symbology uses the naming standards listed in Attachment E, "Symbology."

3.17 Legibility

Drawings must be prepared so that prints are legible when reduced on microfilm and then re-enlarged. As an example, parallel lines have at least 0.06" spacing on the hard copy drawing to maintain distinction. The final released drawing must be capable of passing a fifth-generation copy test (see definition in Section 4.0).

3.18 Drawing List

A drawing list is placed on the first drawing in a project set of 20 or more drawings. The drawing list may be placed on a separate or title sheet. The list contains the following information:

- Drawing numbers
- Drawing index number
- Building numbers (if more than one building is involved in the project)
- Title of each drawing
- Vendor information (VI) lists
- Specifications.

For multiple-sheet drawings, the number of sheets may be shown without repeating the rest of the information (e.g., H-1-12345, SH 6), provided that all the information is identical. When listing a specification or vendor information, the Hanford retrieval number is also listed next to the title.

3.19 Lettering

For CAD-developed drawings, lettering must be all upper case Gothic as defined in ASME Y14.2M, "Line Conventions and Lettering." AutoCAD supplied fonts ROMANS and ROMAND are considered to be in compliance with this requirement. Letter height will be a minimum of 0.12", except where lower case letters or metric symbols are standard (e.g., Na, mm, g). Lower case letters and symbols should be proportional. A minimum height of 0.1" is allowed in cases where smaller letter height is required, such as mapping. Also see Section 3.3.5.

3.20 Drawing Orientation

North should be oriented to the top or left side of the sheet. Exceptions are allowed where modifications are being made to existing facilities for which the orientation of the existing drawings is different or where industry practices dictate (e.g., civil drawings showing plan view strips with corresponding profiles). All plans on a given set of drawings need to be oriented the same and match the existing plant drawing orientation. A north arrow is placed and properly oriented on all maps, plans, layouts, and other drawings depicting spatial orientation.

3.21 Coordinate System and Geodetic Elevation Data

For new construction, the coordinates and elevation are as follows:

- Coordinates - The Washington Coordinate System of 1983, south zone (1991) (WCS83S(1991))
- Elevation Data - The North American Vertical Datum of 1988 (NAVD88).

3.22 Parts/Material List

A parts/material list is used on fabrication and assembly drawings, but not on project construction drawings as depicted on Figure 12 (see also Attachment F).

3.22.1 Arrangement and Size

The minimum width of the Parts/Material List block having one quantity column is 9.5" (see Figure 13). Quantity columns may be added as necessary. The parts/material list is located, or begins, in the upper right-hand corner on the first sheet of the drawing.

3.22.2 Contents

The parts/material list contains all material and separable components on the drawing. The individual pieces of weldments or other inseparable assemblies normally are not numbered separately.

3.22.3 Part Arrangement/Order


The parts/material list should be arranged in a hierarchy (i.e., assemblies, subassemblies, detail parts, catalog items). It is not necessary to rearrange the parts/material list merely to add a later entry.

Figure 12. Drawing Types and Classifications.

Engineering Drawing Type	Parts/Material List Not Used	Formal Parts/Material List, Required (See Code Key Below)	Material Call-out on Field of Drawing (See Code Key Below)
Architectural			All
Civil			All
Structural		1	2
Electrical		1-2-4	7
Piping		1-3-5	2
Instrumentation		1-2-3-4	7
Heating, Ventilation, and Air Conditioning		1-3-8	2-7
Mechanical		1	2
DRAWING CLASSIFICATION			
Fabrication		All	
Construction		6	All
Altered Item		1	2
Specification Control			All
Non-Fabrication/Construction, i.e., maps, conceptual layouts, cell arrangements, diagrams, schematics, wire run list, drawings made for operational use.	All		

1. Fabrication or shop-oriented drawings.
2. Construction field-installation-oriented drawings.
3. In parts/material list description column, enter all pipe ells, tees, etc., as “size of pipe and miscellaneous fittings.”
4. In parts/material list description column, enter all conduit lugs, pull boxes, etc., as required by National Electrical Code.
5. Prefabricated.
6. Electrical, instrumentation, and HVAC disciplines (non-project).
7. Project construction type drawings only.
8. Process hood systems (supply and exhaust) and process exhaust systems drawings only.

Figure 13. Parts/Materials List Placement.



3.22.4 Part Number

Unique part numbers are assigned where a design configuration (i.e., assembly, subassembly, and detail) is controlled on an H-series drawing. A part number is used to uniquely identify a specific item. Items that are not interchangeable are identified with separate and unique part numbers.

The official part number is the drawing number and the assigned dash number (see Section 4.0). When a part number is referenced, both the drawing number and the dash number are identified.

3.22.5 Parts and Assembly Numbers

Each assembly, subassembly, and detailed part is assigned a separate and unique part (dash) number. The primary assembly is assigned the -010 dash number. Additional assemblies and subassemblies are assigned every tenth number consecutively (e.g., -020, -030, -040, etc). The first detailed part is assigned the -001 dash number. Additional detailed parts are assigned -002, -003, -004, etc., with every tenth digit reserved for assemblies.

3.22.6 Interchangeable Parts

Interchangeable parts are equivalent in performance and durability. They are capable of being exchanged one for the other without alteration of the item or of adjoining items, except for nominal adjustment. They are also interchangeable in terms of fit and performance. Interchangeability is also explained in general notes with a statement in the parts/material list to see the applicable general note.

3.22.7 Part Number Revisions

The parts/materials list periodically requires revisions and/or material deletions due to fabrication changes or modifications to the original design. The following are accepted methods for changing the parts/material list, when accompanied by an Engineering Change Notice (ECN):

- Remove a part or material item by placing a double line through the part or material item (e.g., CAD or manual drawings).
- Remove a part or material item and add the word “Deleted” in place of the part or material item (e.g., CAD revision).

3.22.8 New Part Number

New part numbers, including applicable altered item part numbers (see section 3.22.10), are assigned when the design of a part, fabricated assembly, or procured item is changed so that any of the following conditions could result:

- Performance or durability is affected to the extent that superseded items must be discarded for reasons of safety, failure, or malfunction.
- Parts, assemblies, or subassemblies are changed so that the new designs are not directly and completely interchangeable with respect to installation and/or specified performance.
- When replaced/redesigned parts are limited to use in specific applications and the newly designed items are not so limited.
- When an existing Hanford item, or vendors’ purchased item, requires alteration.
- When existing items cannot be reworked to be directly and completely interchangeable with the new design.

NOTE: New materials are added at the end of the parts/materials list using sequential part numbers. Part numbers cannot be reused for new or different parts/material; new part numbers are required.

3.22.9 Purchased Items

Purchased items are identified in the parts/materials list with the manufacturer’s part number or vendor information (VI) number. These items are normally controlled by the vendor, by industrial or government codes, standards, or file number.

3.22.10 Altered Item

If the design of a vendor-supplied item is altered after purchase for an existing Hanford Site application (documentation may be contained in a VI file), or for use in a new engineering design, the following requirements apply:

- “ALTERED FROM (manufacturer’s part number and part name or existing Hanford part number and part name)” is recorded in the description column of the parts list.
- Assign a new Hanford part number and place it in the part number column.

- The alteration is detailed by visible lines in accordance with ASME Y14.2M. Reference features (features not requiring alteration) are limited to orientation for describing where designated alterations are required. Reference features are shown by phantom lines in accordance with ASME Y14.2M.

3.22.11 Quantities and Customary Trade Units

Quantities are counted accurately and shown in customary trade units.

3.22.12 As Required (AR) Designation

The letters AR (as required) are used where the quantity is not known or where the quantity could vary.

3.22.13 Part Description

The part description should be generic, except where a specific item is required, and the design depends on or is tailored to the specific item. The name of the item is listed first with supplemental descriptive words following. The description of an item must be complete and provide specifications sufficient to procure the item.

Standard industry language is used to define the item. If the item can be completely described in the parts/materials list, it need not be delineated on the drawing. If description/specification is lengthy, it may be in the general notes or in a separate specification. If the description/specification is placed in the general notes or in a separate specification, the general note or separate specification is referenced in the description column of the parts list.

3.23 Component Numbering

Structures, systems, and components are numbered in accordance with standard RPP-8530 and [TFC-OPS-OPER-C-32](#).

Coordinate assignment of component numbers with Base Operations Engineering to avoid duplication of component numbers.

3.24 Measurement System


3.24.1 General

English customary units (inch pound system) are used for measurements shown on drawings, unless otherwise directed by the TOC Chief Engineer. Alternate units, such as metric (SI) equivalents, are not required to be shown. Modifications to drawings that contain English customary units use those units unless otherwise directed.

3.24.2 Metric Notation

If drawings are directed to be done in the metric (SI) system, the word “METRIC” (see Figure 14 and Figure 5) is placed directly above the Title Block in 6 mm bold gothic lettering as defined by ASME Y14.2M.

Figure 14. International Projection Symbol.



3.24.3 Third Angle Projection

All drawings developed using the multi-view system of orthographic presentation as specified in ASME Y14.3M, “Multi and Sectional View Drawings,” are to use the third angle projection method.

3.25 Revisions

3.25.1 Revisions Block Size and Location

The REVISIONS block are sized according to ASME Y14.1, and configured as shown in Figure 15. Location of the block is according to the drawing arrangement format (see Figure 15).

Figure 15. Typical Revision Block.

	MFD	REV NO	DESCRIPTION	REV BY	DATE	ENGR	COMPANY	
	REV REL	REVISIONS						
	CADFILE	CADCODE						
		3						2

ENGINEERING	Document	TFC-ENG-STD-10, REV A-8
	Page	25 of 98
DRAWING STANDARD	Issue Date	November 8, 2011

3.25.2 Description

The authorizing engineering change document is entered in the revision description (e.g., Engineering Change Notice (ECN)). Conservation of space is essential; therefore, ANSI abbreviations are used while keeping the meaning clear.

3.25.3 Revision Numbers

When revising multiple-sheet drawings, each sheet is considered a separate drawing. Revision numbers are advanced only on the sheet or sheets being affected by the change.

3.25.4 Change Incorporation - For Drawings that are Maintained in the Hanford Drawing System

Show the authorizing ECN number in the REVISIONS Block (e.g., REVISED PER ECN (number)).

3.25.4.1 Incorporation of Engineering Change Notices

During ECN incorporation, an additional ECN is not required for the following non-technical changes:

- When adding an additional sheet(s) to an affected drawing as a result of the incorporation of an ECN. Under these circumstances the original ECN being incorporated is the authorizing ECN document.
- Correcting misspelled words.
- Adding or revising related/referenced arrangements, views, sections, details, and/or tables to accurately delineate the approved ECN incorporation on an affected drawing.
- Delineating the ECN incorporation on a subsequent sheet(s) of an affected drawing when there is insufficient space available for depicting the required information.
- A statement describing variances from the authorizing ECN is added in the revision description block to document the changes. Examples are as follows:
 - Incorporated ECN XXXXXX, was sheet 3 of 4
 - Incorporated ECN XXXXXX, moved detail X
 - Incorporated ECN XXXXXX, added detail X due to insufficient space on sheet X
 - Incorporated ECN XXXXXX, added new sheet X.
- Conversion of a manual drawing to a new CAD.DWG file.
- Removing impact levels.

3.25.4.2 Revision Numbering and Release


List each new revision in numerical sequence. Only released (issued) drawings are revised. Each subsequent revision is released before another revision is made. The latest revision number is shown in the Title Block (see Section 3.7.7 and Figure 15).

3.25.4.3 CAD-Revised Drawings

CAD-developed drawings do not require approval signatures from previous revisions to be printed in the spaces of the Title or REVISIONS Block. Reference to see the applicable revision is placed in the approval block (e.g., see Revision 0 or see Revision 5).

On drawings that have a CADFILE and CADCODE the data is to be removed or a strikeout through the text. See Figure 16.

Figure 16. CADCODE and CADFILE Strikeout.



3.25.4.4 Removing Revisions

Drawings in the Hanford system that have been previously approved and microfilmed may have revisions removed from the drawing(s) on subsequent revisions.

3.25.4.5 Revision Documentation and Approval

The responsible engineer signs and enters the company acronym in the ENGR/COMPANY block of the revision block, see Figure 15. Drawing revision requirements and results are documented and approved by an ECN prior to the release of a drawing that has been revised.

3.25.4.6 Change After Approval

Changes made to drawings after approval and before formal release and microfilming require complete re-approval of the drawings. All existing approval signatures and dates are removed and new approval signatures are obtained.

3.25.4.7 Adding Additional Sheets

Additional sheet(s) that are added are released as revision "0." The ECN number being incorporated is placed in the block identified for the Engineering Data Transmittal (EDT). The letters EDT are removed or marked out and the number placed in this block (e.g., ECN number).

3.26 Official Use Only and Export Controlled Drawings

The originating organization marks the drawing in accordance with TFC-BSM-IRM_SE-C-05 to reflect OUO or ECI markings or other required controls as needed; contacts Subject Mater Experts, Derivatives Classifiers, or Legal Services as required to establish accountability; and protects the document using security and handling requirements appropriate for the level marked on the drawings.

3.27 Superseded Drawings, Voided Drawings, and Title Block Changes

When drawings are superseded or voided, or when a building, index, or drawing number is changed, the affected drawings are revised with an ECN.

3.27.1 Superseding a Drawing with a Different Drawing Number

3.27.1.1 The Superseded Drawing

A note stating, "SUPERSEDED BY DWG (number) REV.(number)," is placed near the Title Block in 0.24" high lettering.

3.27.1.2 The New Drawing

A note stating, "SUPERSEDES DWG (number) REV. (number)," is placed near the Title Block in 0.24" high lettering.

3.27.2 Superseding an Approved Drawing with a Drawing of the Same Drawing Number (Redraw)

The conversion of a manual drawing to an AutoCAD file does not require the use of an ECN. For these drawing conversions, the drawing revision number shall be incremented, and the revision description on the drawing sheet shall include the following description: "Manual to AutoCAD conversion". (Revision of a CAD.DWG file is not a redraw. Development of a new CAD .DWG file from an existing released drawing is a redraw.)

3.27.3 Voided Drawings

Place the word "VOID" near the Title Block in 0.5" high lettering. The revision of the drawing is advanced with the authorizing ECN number identified in the REVISIONS Block (e.g., VOID PER ECN number). The use of a microfilm copy of the affected drawing may be used in place of the original drawing for this voiding process.

3.27.4 Changing Drawing Numbers, Index Numbers, or Building Numbers

3.27.4.1 Changing Index Numbers

Add or delete additional Index Numbers by revision of the drawing.

3.27.4.2 Changing Building Numbers

Add or delete Building Numbers by revision of the drawing.

3.28 Changing the Title of a Drawing

Changes in the title of an approved drawing require a revision. All current requirements apply to revised drawing titles (see Section 3.7.3).

3.29 Interface Control

Interface control is the establishment and preservation of design features between co-functioning systems or components shared typically by two or more contractors or projects. This design interface information is identified on the appropriate engineering drawing(s) by an interface control symbol. The interface control symbol (defined on drawing H-14-020000, sheet 4) is used to recognize and maintain the compatibility of the design features at these interface boundaries that require control. This symbol provides the physical location for the design features (e.g., electrical terminations, power requirements, size and locations of connection points, flow rates) that are subject to control.

Two methods are available to depict the interface control boundary and their associated design features. The first and preferred method is to display the interface control symbol at the appropriate drawing location. The symbol includes a reference to the unique and retrievable number of the authorizing interface control document (ICD); e.g., ICD 01. This referenced ICD provides the detailed information on the design features for this controlled interface.

The second method should only be used when an authorizing ICD does not exist, or when the controlled interface contains minimum (three or less) design features. When using the second method, the responsible organization (owner) is also identified either at the location of the interface control symbol or in the General Notes section of the drawing. For a complex interface that exceeds these maximum three design features, an ICD is created.

Add an interface control note to the General Notes section of the affected drawing (applies to either method used) to identify that the information on this drawing contains controlled interface design features. This general note should read as follows:

“Interface control information impacted on this drawing requires change approval.”

4.0 DEFINITIONS

Altered-tem drawing. An engineering drawing used to control and depict the alterations to a commercial item. An altered-item drawing reflects only the change and is not intended to show complete fabrication details.

Applied material. Material that is not normally shown on the graphic presentation of a drawing (e.g., glues, adhesive, paint, cleaner). It may or may not have a manufacturer’s identification number. Applied material normally is identified in the General Notes and its application explained, as required. Weld rod is excluded from this definition.

Arrangement/Installation drawing. The top level drawing where multiple related details, assemblies, subassemblies, and certain connecting parts and/or instructions are shown depicting the final arrangement.

As required (AR). A notation used when an exact quantity is not known or cannot be easily predetermined. The notation is placed in the “Quantity Required” column of the parts list.

Assembly. A term used to describe parts and/or subassemblies joined to complete a designed relationship.

NOTE: In view of the difficulty, in some cases, in establishing a clear distinction between the terms “assemblies” and “sub-assemblies,” these two terms may be considered to have the same meaning and may be used interchangeably.

Brand name. Brand name implies the manufacturer, model, catalog name/number, trademark, or identifying name other than generic.

Computer-Aided Design (CAD) Data Set. The CAD data set is the computer data file used to produce a hard copy engineering drawing.

Dash number. A dash number is a unique numerical identification assigned to an item whose design is controlled by the drawing. When suffixed to the drawing number, the dash number provides a unique part number (see Part Number definition) for that item. A dash number is assigned where two or more items or an assembly are depicted on a drawing. The dash number will consist of three digits and be assigned as follows:

1. Assemblies. Every tenth number is reserved for assemblies (e.g., -010, -020, -030, -040).
2. Parts. -001 for the first part and consecutively for all others, reserving every tenth number for assemblies (e.g., -001 through 009; -011 through -019; etc.).

Detailed (piece parts) item. An individual item or units of material that requires specific part (dash) number identification because of traceability and accountability requirements for that item.

Fifth-generation copy test. For the purposes of this standard, a fifth-generation copy test consists of making a full size copy (first-generation copy) from the original document, using a high quality copier. Then making a copy of the copy (second-generation); then a copy of that copy (third-generation copy), etc., until the fifth-generation copy is achieved. The graphics and text of the fifth-generation copy must be clearly legible without magnification, special lenses, or editing.

Hardware item. Fasteners that may or may not require material identification (e.g., ASTM, and SAE).

Inch/Pound measurement. Inch/pound measurements are units of the English measurement system (e.g., inches, pounds, degrees Fahrenheit, gallons). The formally recognized inch/pound units are the foot and the pound as defined by the National Institute of Standards and Technology (NIST).

Inseparable assembly. Parts/material joined in such a manner that they are incapable of being disassembled without destroying the intended function of the item (e.g., weldments, bonded assembly).

Item number. A number assigned to every line entry of a Parts/Materials Lists to tabulate items in the list. It is also used to locate an item in the field of the drawing and is not used for unique identification purposes.

Material item. Material used in an inseparable assembly whose final configuration is contained within the configuration of that assembly (e.g., a weldment). Also, see Inseparable Assembly definition.

Part number. A part number consists of letters, numbers, or combinations of letters and numbers, that may or may not be separated by dashes and are assigned to uniquely identify a specific item. Part Numbers assigned to Hanford “H” series drawings consist of the drawing number plus a dash number.

EXAMPLE: H-3-60670-010
-010 is the Dash Number
H-3-60670 is the Drawing Number

Parts/Materials list. A tabulation of parts and/or material required for constructing, fabricating, or procuring the items depicted on a drawing.

Subassembly. An assembled unit designed to be incorporated with other units (see Assembly definition).

X-Reference. This is an AutoCAD program feature that allows drawing data to be shared between data files. The shared data is not permanently part of the drawing until the X-Reference data is bound into the master (main) data file.

5.0 SOURCES

5.1 Requirements

1. Contract number DE-AC27-08RV14800.
2. DOE O 252.1, “Technical Standards Program.”
3. TFC-PLN-02, “Quality Assurance Program Description.”
4. TFC-PLN-03, “Engineering Program Management Plan,” Section 5.0, Table 1.

5.2 References

1. ANSI Y14.38 (latest edition), “Abbreviations and Acronyms.”
2. ANSI Y14.1 (latest edition), “Decimal Inch Drawing Sheet Size and Format.”
3. ANSI Y14.5M (latest edition), “Dimensioning and Tolerancing.”
4. ASME Y14.2M (latest edition), “Line Conventions and Lettering.”
5. ASME Y14.3M (latest edition), “Multi and Sectional View Drawings.”
6. TFC-BSM-IRM_SE-C-05, “Marking Sensitive Unclassified Information.”
7. TFC-ENG-DESIGN-C-06, “Engineering Change Control.”
8. TFC-ENG-DESIGN-C-09, “Engineering Drawings.”

9. TFC-BSM-IRM_DC-C-02, "Records Management."

ATTACHMENT A – GUIDE TO HISTORICAL DRAWING NUMBERS

The Hanford drawing system has a legacy of drawings that do not conform to current practices. This guide will assist in interpreting the drawing numbering system from the early days of Hanford and from irregularities in the drawing tracking system

A. The following designations are a legacy of Hanford’s early days.

- AEC - Used for 700 and 1100 Areas (Atomic Energy Commission drawing file)
- SP and P - Used for 100 H and 100 C Areas
- M-Series - Used for Hanford area maps
- D and W - Used for original DuPont drawings (W = Arrangements/Profiles; D = Details)
- SK-Series - Assigned to temporary drawings for off-site procurement, experimental equipment, limited-use test equipment and conceptual designs.

The 400 Area, FFTF facility, has a number of Architectural-Engineering (A-E) drawings that have various drawing number assignments. These drawings are maintained as a special case in the Hanford drawing system. Some examples of the drawing numbers are: 00369, 30703726-000, 375, 6083-01-301, 671C499, 6MD13007-2D1, A888-6001, AA-4698, P-C418, SKT-241, T73065-300, W-22027-17-20, W-26007, S-06-07-1.

NOTE: Drawing prefixes AEC, SP, P, M, D, W, and SK are record drawings only; all new drawings use an “H” prefix.

B. Drawing number irregularities include the following:

- Certain 202-A building drawing numbers (200 Area) -

Example: H-2-53505-M. Disregard the letter designator “M” in this example. These letters are to be removed as part of the next regular revision. New drawings calling out these drawings as a reference will omit the letter designator.

- Certain 222-S, 284-E, and 284-W building drawing numbers (200 Area) -
Example: H-II-4428-10.

The “H-II” was intended to be Roman numeral II, and may be confused with “H-11” (1100 Area drawings). The “-10” suffix is the sheet number. All references to these drawings on new drawings should be, for example, “H-II-4428 sheet 10.” Revisions to these drawings do not require that the Roman numerals be changed to Arabic. New drawings developed for these buildings use “H-2” prefixes and conventional sheet identification.

- Certain “H-4” drawings and some early instrument drawings using “H-4” drawing numbers were used for site-wide applications.

ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY DISCIPLINE

**Table B-1. Startup Layer Naming Standard -
General Layering For All Disciplines**

Note: Selected layers from the general layering for all disciplines are added to the drawing setup models as necessary to define and separate drawing data.

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
AUTOCAD PROGRAM				
0	AutoCAD generated. Not for project drawings; used for standard symbol creation	White	Continuous	Pen No. 2
DEFPOINTS	AutoCAD generated; associative dimensioning definition points automatically on this layer; used for display only, as AutoCAD will not print.	White	Continuous	Pen No. 2
GENERAL LAYERS				
?O-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
?M-DIM	Dimensioning	253	Continuous	Pen No. 1
?T-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
?T-BTXT	Bold text	Yellow	Continuous	Pen No. 4
?T-REF	Reference items and notes that aid CAD users during construction of the drawing	213	Continuous	Pen No. 1
?T-CHK	Checker's marks (informal only)	11	Continuous	Pen No. 3
?O-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
?O-CLD	Clouded areas for Hold, ECN, and revision	White	Continuous	Pen No. 2
?E-EXST	Anything existing to remain	8	Phantom	Pen No. 1
?D-DEMO	Existing items /equipment required to be removed or demolished	Cyan	HiddenX2	Pen No. 3
?C-CLINE	Center line	Blue	Center	Pen No. 2
?X-HATCH	Cross-section lines	Blue	Continuous	Pen No. 2
?H-HIDL	Hidden lines	Blue	Hidden	Pen No. 2
?V-MLN	Matchlines	Red	Phantom	Pen No. 5

¹ The “?” is replaced with the correct Discipline Identifier; see Section 3.3.2.

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-2. Startup Layer Naming Standard -
Architectural Drawings**

Note: When additional layers are created to specify discipline information, other than architectural, the object/function identifier from the appropriate discipline table should be used to define the drawing data. The architectural discipline identifier should be used and the applicable plotter pen number assigned.

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
AO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
AM-DIM	Dimensioning	253	Continuous	Pen No. 1
AT-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
AT-BTXT	Bold text	Yellow	Continuous	Pen No. 4
AT-REF	Reference items and notes that aid CAD users during construction of the drawing	213	Continuous	Pen No. 1
AO-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
AO-CLD	Clouded areas for Hold, ECN, and revision	White	Continuous	Pen No. 2
AE-EXST	Anything existing to remain	8	Phantom	Pen No. 1
AD-DEMO	Existing items /equipment required to be removed or demolished	Cyan	HiddenX2	Pen No. 3
AX-HATCH	Cross-section lines	Blue	Continuous	Pen No. 2
AV-MLN	Matchlines	Red	Phantom	Pen No. 5
SPECIFIC LAYERS				
AO-ACCESSORY	Accessory items - including furniture, HVAC equipment, plumbing fixtures, people, trees, vehicles, etc.	White	Continuous	Pen No. 2
AO-CEILING	Ceiling - SATC, hanger wires, etc.	White	Continuous	Pen No. 2
AC-COLUMN	Building column lines	White	Center	Pen No. 2
AO-DOOR	Interior and exterior	Magenta	Continuous	Pen No. 2
AO-DOORSPEC	Door tag (Architectural Steering Group users only)	White	Continuous	Pen No. 2
AO-FLOOR	Floor plan and background	8	Continuous	Pen No. 2

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-2 (cont.) Startup Layer Naming Standard -
Architectural Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
SPECIFIC LAYERS (Continued)				
AO-HEADER	Door header (use with ceiling plan)	White	Continuous	Pen No. 2
AO-SCHEDULE	Room, door, finish, and window	Cyan	Continuous	Pen No. 3
AO-STAIR	Interior and exterior	White	Continuous	Pen No. 2
AO-TAG	Tags for miscellaneous equipment, windows, etc.	White	Continuous	Pen No. 2
AO-WALLS	Interior and exterior	Cyan	Continuous	Pen No. 3
AO-WINDOWS	Interior and exterior	White	Continuous	Pen No. 2

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-3. Startup Layer Naming Standard -
Civil/Structural/Environmental Drawings**

Note: When civil and structural items exist in the same drawing, use both layer naming standards.

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
?O-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
³ ?T-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
³ ?T-REF	Reference items and notes that aid CAD users during construction of the drawing	213	Continuous	Pen No. 1
³ ?O-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
³ ?V-MLN	Matchlines	Red	Phantom	Pen No. 5
Specified general layers are used in both the civil and structural drawings. The “?” is replaced with the correct discipline identifier; see Section 3.3.2.				
CIVIL DRAWING SPECIFIC LAYERS				
CO-GRID	Site Grids, Profile Grids, etc.	253	Continuous	Pen No. 1
CO-SITE	Property lines, boundaries, fences, etc.	60	Continuous	Pen No. 4
CO-ROAD	Roads, trails, parking, etc.	10	Continuous	Pen No. 4
CO-STRL	Structural work	210	Continuous	Pen No. 4
CO-GND	Contours, grade breaks, etc.	Green	Continuous	Pen No. 4
CO-EX-CONT	Existing contours	252	Continuous	Pen No. 2
CO-NEW-CONT	New contours	92	Continuous	Pen No. 2
CO-PIPE	Pipelines and piping	Yellow	Continuous	Pen No. 4
STRUCTURAL DRAWING SPECIFIC LAYERS				
SC-GRID	Building column grid	253	Center	Pen No. 1
SO-GND	Grade or earth shown on sections	Green	Continuous	Pen No. 4
SO-CONC	Concrete	Yellow	Continuous	Pen No. 4
SO-FRWK	Framework	Cyan	Continuous	Pen No. 3
SO-RBR	Rebar	130	Continuous	Pen No. 4
SO-MECH	Piping or other mechanical	11	Continuous	Pen No. 3
SO-EMBED	Embedments	131	Continuous	Pen No. 3
SO-STL	Steel	130	Continuous	Pen No. 4

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-4. Startup Layer Naming Standard -
Electrical Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
EO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
EM-DIM	Dimensioning	253	Continuous	Pen No. 1
ET-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
ET-BTXT	Bold text	Yellow	Continuous	Pen No. 4
LIGHTING/SITE DRAWING SPECIFIC LAYERS				
EE-BKG	Background	8	Phantom2	Pen No. 1
EO-BLD	Building	171	Continuous	Pen No. 3
EO-CND	Conduit, cable, raceway, boxes, ductbanks	51	Continuous	Pen No. 3
EO-CPT	Cathodic protection	11	Continuous	Pen No. 3
EO-EQP	Equipment	211	Continuous	Pen No. 3
EO-LTG	Lighting	Cyan	Continuous	Pen No. 3
EO-MS1	Electric miscellaneous 1	32	Continuous	Pen No. 2
EO-MS2	Electric miscellaneous 2	51	Continuous	Pen No. 3
EO-OHD	Overhead lines	11	Continuous	Pen No. 3
EO-RCP	Receptacles, (120, 208, 480V)	Cyan	Continuous	Pen No. 3
EO-SGD	Signaling devices	211	Continuous	Pen No. 3
EO-UGD	Underground lines (hidden)	13	Hidden	Pen No. 1
DIAGRAM/SCHEDULE DRAWING SPECIFIC LAYERS				
EO-DIA	Diagrams, one-line, elementary, etc.	91	Continuous	Pen No. 3
EO-MS1	Electric miscellaneous 1	32	Continuous	Pen No. 2
EO-MS2	Electric miscellaneous 2	51	Continuous	Pen No. 3

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-5. Startup Layer Naming Standard -
Fire Protection Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
FO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
FM-DIM	Dimensioning	253	Continuous	Pen No. 1
FT-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
FT-BTXT	Bold text	Yellow	Continuous	Pen No. 4
FE-EXST	Anything existing to remain	8	Phantom	Pen No. 1
FD-DEMO	Existing items /equipment required to be removed or demolished	Cyan	HiddenX2	Pen No. 3
FC-CLINE	Center line	Blue	Center	Pen No. 2
FV-MLN	Matchlines	Red	Phantom	Pen No. 5
FIRE DETECTION DRAWING SPECIFIC LAYERS				
FO-AD	Alarm and detection system	211	Continuous	Pen No. 3
FO-FW	Fire water underground	211	Hidden	Pen No. 3
SPRINKLER DRAWING SPECIFIC LAYERS				
FO-FW	Fire water underground	211	Hidden	Pen No. 3
FO-SS	Sprinkler system	211	Continuous	Pen No. 3
FO-HS-1	Standpipe hose system	211	Continuous	Pen No. 3

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-6. Startup Layer Naming Standard -
HVAC Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
HO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
HM-DIM	Dimensioning	253	Continuous	Pen No. 1
HT-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
HT-BTXT	Bold text	Yellow	Continuous	Pen No. 4
HT-REF	Reference items and notes that aid CAD users during construction of the drawing	213	Continuous	Pen No. 1
^s HO-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
HV-MLN	Matchlines	Red	Phantom	Pen No. 5
HVAC DRAWING SPECIFIC LAYERS				
HO-EQP	HVAC or piping equipment	51	Continuous	Pen No. 3
HO-EXH	HVAC exhaust system	171	Continuous	Pen No. 3
HO-PIP	Piping and piping fixtures and hardware	51	Continuous	Pen No. 3
HO-PLM	Plumbing and plumbing fixtures and hardware	201	Continuous	Pen No. 3
HO-RTN	HVAC return system	Cyan	Continuous	Pen No. 3
HO-SUP	HVAC supply system	51	Continuous	Pen No. 3
HVAC/INSTRUMENTATION DRAWING SPECIFIC LAYERS				
IO-ELEC	Electrical equipment	71	Continuous	Pen No. 3
IO-DCS	Distributed control system instruments	Cyan	Continuous	Pen No. 3
IO-ELINE	Electrical signal lines	42	Hidden	Pen No. 2
IO-ILINE	Instrument lines, such as pneumatic	Magenta	Continuous	Pen No. 2
IO-CVAL	Control valves	Cyan	Continuous	Pen No. 3
IO-SLINE	Software link line	Magenta	Continuous	Pen No. 3

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-7. Startup Layer Naming Standard -
Instrumentation & Control (I&C) Drawings**

*Note: When creating additional layers to specify existing
and future layers, the preferred color is 8, which is
designated to Plotter Pen No. 1.*

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
IO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
IM-DIM	Dimensioning	253	Continuous	Pen No. 1
IT-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
IT-BTXT	Bold text	Yellow	Continuous	Pen No. 4
IT-REF	Reference items and notes that aid CAD users during construction of the drawing	213	Continuous	Pen No. 1
IT-CHK	Checker's marks (informal only)	11	Continuous	Pen No. 3
IO-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
IO-CLD	Clouded areas for Hold, ECN, and revision	White	Continuous	Pen No. 2
IE-EXST	Anything existing to remain	8	Phantom	Pen No. 1
ID-DEMO	Existing items /equipment required to be removed or demolished	Cyan	HiddenX2	Pen No. 3
IC-CLINE	Center line	Blue	Center	Pen No. 2
IX-HATCH	Cross section lines	Blue	Continuous	Pen No. 2
IH-HIDL	Hidden lines	Blue	Hidden	Pen No. 2
IV-MLN	Matchlines	Red	Phantom	Pen No. 5
P&ID DRAWING SPECIFIC LAYERS				
IO-ELEC	Electrical equipment	71	Continuous	Pen No. 3
IO-INS	Instruments	211	Continuous	Pen No. 3
IO-DCS	Distributed control system instruments	Cyan	Continuous	Pen No. 3
IO-ELINE	Electrical signal lines	42	Hidden	Pen No. 2
IO-ILINE	Instrument lines, such as pneumatic	Magenta	Continuous	Pen No. 2

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-7 (cont.) Startup Layer Naming Standard -
Instrumentation & Control (I&C) Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
P&ID DRAWING SPECIFIC LAYERS (Continued)				
IO-CVAL	Control valves	Cyan	Continuous	Pen No. 3
IO-SLINE	Software link line	Magenta	Continuous	Pen No. 3
IO-EQP	Equipment	141	Continuous	Pen No. 3
IO-MAJ	Major process lines	Red	Continuous	Pen No. 5
IO-MIN	Minor process lines	Yellow	Continuous	Pen No. 4
IO-PROC	Process line	152	Continuous	Pen No. 2
IO-PIP	Piping valves and fittings	121	Continuous	Pen No. 3
PLANS, ELEVATIONS, DETAILS, AND ASSEMBLY DRAWING SPECIFIC LAYERS				
IO-TUBE	Tubing	52	Continuous	Pen No. 2
IO-BGND	Background	8	Continuous	Pen No. 1
IO-PIPE	Piping	12	Continuous	Pen No. 2
IO-BLDG	Building	8	Continuous	Pen No. 1
IO-EQP	Equipment	143	Continuous	Pen No. 1
IO-INS	Instruments	210	Continuous	Pen No. 4
IO-FRM	Panels, racks, cabinets	32	Continuous	Pen No. 2
IO-WRG	Wiring	92	Continuous	Pen No. 2
IO-CVAL	Control valve	130	Continuous	Pen No. 4
WIRING/TUBING DIAGRAM DRAWING SPECIFIC LAYERS				
IO-WRG	Wiring	Green	Continuous	Pen No. 4
IO-INS	Instruments	Magenta	Continuous	Pen No. 2
IO-DCS	Distributed control system instruments	132	Continuous	Pen No. 2
IO-TBLK	Terminal blocks	152	Continuous	Pen No. 2
IO-SLINE	Software lines	12	Continuous	Pen No. 2
IO-TUBE	Tubing	Yellow	Continuous	Pen No. 4
LOGIC/BLOCK DIAGRAM DRAWING SPECIFIC LAYERS				
IO-GATE	Logic gate/memory latch	Green	Continuous	Pen No. 4
IO-SPATH	Software signal path	12	Continuous	Pen No. 2
IO-HPATH	Hardware signal path	152	Continuous	Pen No. 2
IO-INS	Instruments	211	Continuous	Pen No. 3
IO-DCS	Distributed control system instruments	Cyan	Continuous	Pen No. 3

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-8. Startup Layer Naming Standard -
Mechanical Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
GENERAL LAYERS				
MO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
MM-DIM	Dimensioning	253	Continuous	Pen No. 1
MT-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
MT-BTXT	Bold text	Yellow	Continuous	Pen No. 4
MT-CHK	Checker's marks (informal only)	11	Continuous	Pen No. 3
MO-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
MC-CLINE	Center line	Blue	Center	Pen No. 2
MX-HATCH	Cross-section lines	Blue	Continuous	Pen No. 2
MH-HIDL	Hidden lines	Blue	Hidden	Pen No. 2
MV-MLN	Matchlines	Red	Phantom	Pen No. 5
SPECIFIC LAYERS				
MO-1DET	Detail	Yellow	Continuous	Pen No. 4
MO-2DET	Detail	Green	Continuous	Pen No. 4
MO-FAST	Fasteners	Cyan	Continuous	Pen No. 3
MO-VEND	Vendor information	8	Continuous	Pen No. 1
MP-PHANT	Moving parts, alternate positions, simplified drafting techniques, e.g., screw threads, springs	8	Phantom	Pen No. 1
MO-LAYOUT	Layout and/or construction lines	Magenta	Continuous	Pen No. 2

**ATTACHMENT B – LAYER NAMING STANDARDS FOR AUTOCAD DRAWINGS BY
DISCIPLINE (cont.)**

**Table B-9. Startup Layer Naming Standard -
Piping Drawings**

LAYER NAME	DESCRIPTION	LINE COLOR	LINETYPE	PLOTTER PEN NUMBER
PIPING DRAWING, JUMPER ASSEMBLY 1 DRAWING, JUMPER ASSEMBLY 2 DRAWING, and JUMPER ASSEMBLY 3 DRAWING GENERAL LAYERS				
PO-BRD	Title block, associated blocks, and drawing border	132	Continuous	Pen No. 2
PM-DIM	Dimensioning	253	Continuous	Pen No. 1
PT-TXT	General text not associated with a specific layer	White	Continuous	Pen No. 2
PT-BTXT	Bold text	Yellow	Continuous	Pen No. 4
PT-REF	Reference items and notes that aid CAD users during construction of the drawing	213	Continuous	Pen No. 1
PO-VPT	Paper space Viewport border	White	Continuous	Pen No. 2
PO-CLD	Clouded areas for Hold, ECN, and revision	White	Continuous	Pen No. 2
PE-EXST	Anything existing to remain	8	Phantom	Pen No. 1
PD-DEMO	Existing items /equipment required to be removed or demolished	Cyan	HiddenX2	Pen No. 3
PC-CLINE	Center line	Blue	Center	Pen No. 2
PX-HATCH	Cross-section lines	Blue	Continuous	Pen No. 2
PH-HIDL	Hidden lines	Blue	Hidden	Pen No. 2
PV-MLN	Matchlines	Red	Phantom	Pen No. 5
SPECIFIC LAYERS				
PO-PIPINGS	Single-line pipe, valves and fittings	Yellow	Continuous	Pen No. 4
PO-PIPINGD	Double-line pipe, valves and fitting	52	Continuous	Pen No. 2
PO-EQP	Pumps, vessels, etc.	Magenta	Continuous	Pen No. 2
PO-GND	Grade	8	Continuous	Pen No. 1
PO-CONC	Concrete	8	Continuous	Pen No. 1
PO-STRUCT	New structures	8	Continuous	Pen No. 1
PO-PSUPT	Supports	White	Continuous	Pen No. 2

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING**

- A -

Accelerator - Instruments.....	60--50
Acidity - Instruments	6016
Acids, Steam, Air, Gas, Outside Lines - Civil	0308
Acids, Steam Air, Gas Overhead Lines, Piping - Civil	0300
Acids, Steam, Air, Gas, Underground Lines - Civil	0306
Air Conditioning Systems-Plans, Sections, Details - Air Conditioning	9000
Airport Runways, Roads, Walks, Parking Areas, Fences-Details and Profiles - Civil	0200
Alarm - Instrumentation.....	60--43
All Facilities Built into Pile for Testing Purposes - Mechanical	2301
All Test Equipment Where Operation of Pile is Essential to Operation of Test - Mechanical.....	2300
Alpha - Instrumentation	60--51
Aluminum Component Preparation Caps and Can Cleaning Machine, Methanol Still, DetrexTrichlor Still, Trays, Baskets, Racks - Mechanical.....	490104
Aluminum Uranium Fuel Elements and Related Components-Caps, Spires, Cans, Sleeves, Cores, Hollow Pieces, or Perfs, Dummies, Spaces, Wafers, Self-Support - Mechanical	490010
Amplifier - Instrumentation	60--52
Analyzer - Instrumentation	60--53
Aqueous Make-Up - Instrumentation	59--21
Architectural Doors-Shielding-Windows - Architectural	0803
Architectural Equipment Locations - Architectural.....	0804
Architectural-Evaluations, Section and Details-Miscellaneous Steel for Stairs, Railing, etc. - Architectural.....	0801
Architectural-Other (includes schedules, architectural equipment details, such as bins, signs, cabinets, laboratory equipment, etc.) - Architectural	0802
Architectural-Plans-May Include Other.....	0800
Category - Architectural	0800
Area Electrical Key Maps - Civil.....	0102
Argon Systems - Instrumentation	59--46

- B -

Baskets, Tubes, Containers, and Component Parts - Mechanical.....	500304
---	--------

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Billet Core Preparation - Mechanical.....	490110
Biological and Thermal Shield T/C System - Instrumentation	59--16
Block Outs, Sleeves, Plans, and Details - Electrical	7101
Boring, Rock - Civil.....	0600
Burial Grounds Sodium Disposal Area - Civil	0404

- C -

Cable Schedulers - Instrumentation	5904
Calculator - Instrumentation	60--54
Calculator-Power - Instrumentation.....	59--14
Calibrator - Instrumentation.....	60--55
Camera - Instrumentation	60--56
Canning Cycle Control, Flex-O-Timer, Valves, etc. - Mechanical.....	490206
Canning Furnace and Equipment-Canning Jacks, Canning Baskets, Tongs, Shields, Tools - Mechanical	490204
Capsule, Storage for Cesium - Mechanical.....	4921
Capsule, Storage for Strontium - Mechanical.....	4902
Cathodic Protection-Junction Pull Boxes, Ducts - Electrical.....	7806
Cathodic Protection-Plans, Elevations, Sections, and Details - Electrical.....	7801
Cathodic Protection-Wiring Diagrams (elementary, connection and inter-connection) Block Diagrams - Electrical.....	7802
Cell Equipment Fastened to Cell for Mounting Vessels, Nozzles, Dunnage, Y Pads, etc. - Mechanical.....	2800
Ceramic Fuel Elements and Related Components - Mechanical	490030
Chambers - Instrumentation.....	60--57
Charging Machines - Mechanical	2400
Checkers - Instrumentation	60--58
Chemical Storage - Instrumentation	59--30
Chemical Tanks and Piping - Mechanical	490118
Conductivity - Instrumentation	6008
Co-extrusion Component and Billet Assembly - Mechanical.....	490220
Columns, Tanks, Dissolvers, Heat Exchangers, Vessels (no moving parts) - Mechanical.....	2500

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Communication-Junction Pull Boxes, Ducts (this series includes sound-powered telephone and central station system telephones) - Electrical	7606
Communications-Panel Schedules, Equipment, and Devices - Electrical	7604
Communications-Plans, Elevations, Sections, and Details - Electrical	7601
Communications-Station Schedules - Electrical.....	7607
Communications-Wire Run Lists, Conduit, Wire Schedules, Cables - Electrical	7605
Communications-Wiring Diagrams (elementary, connections and inter-connections) Block Diagrams - Electrical	7602
Component Electronic or Ultrasonic Testing-Transformation Tests, Sort Tester, etc. - Mechanical.....	490304
Component Mechanical Inspection-Pickle Inspection Statistical Sampling, Recovered Core Inspection, Gauges - Mechanical	490302
Component of a Mixture - Instrumentation	6020
Composite-Overhead and underground Piping - Civil.....	0305
Concrete Structural-Demolition - Architectural	0905
Concrete Structural-Elevations, Sections and Details - Architectural	0901
Concrete Structural-Penetrations, Emedment Schedules - Architectural	0904
Concrete Structural-Penetrations, Sleeve and Blockout - Architectural	0903
Concrete Structural-Plans - Architectural	0900
Concrete Structural-Shop, Reinforcing and Pour Drawings - Architectural.....	0902
Containers for Disposal of Contaminated Equipment (does not include metal handling buckets and shipping casks) - Mechanical.....	2302
Control Rod, Absorber, Drive, and Disconnect - Mechanical	1907
Control Rods-Assembly Tooling and Handling Equipment - Mechanical	1906
Control Rods - Mechanical	1905
Control Room and Miscellaneous Instrumentation	59--44
Control System-Horizontal Rods - Mechanical	1900
Control System-Poison - Mechanical	1902
Control System-Vertical Rods - Mechanical	1901
Controller - Instrumentation	60--41
Core Preparation-Pickle Machine-Etch Machine, Nickel Plating - Mechanical.....	490102

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Counters - Instrumentation	60--59
Cranes (all Types) - Mechanical	3900
Crane Doors, Shielded, Non-Shielded	3903
Criticality Monitoring Systems - Electrical	7900

- D -

Density - Instrumentation	6005
Differential Pressure - Instrumentation.....	6015
Digital Data Handling and Display, System 91 - Instrumentation.....	59—61
Discharging and Manipulator for Rear Face Work - Mechanical.....	2401
Dissolver Cells - Instrumentation	59--19
Dissolvers, Heat Exchangers, Vessels, Columns, Tanks (no moving parts) - Mechanical.....	2500
Drawing List - Civil.....	0000
Duplex Furnace and Equipment-Ajax Induction Furnaces, Duplex Agitators, Agitator Baskets, Loader Shields, Tools - Mechanical	490202

- E -

Electrical Control-Control Panel Arrangements, Signal Plans, Elevations, Section, and Details - Electrical	7501
Electrical Control-Control Equipment and Devices -Electrical.....	7508
Electrical Control-Junction Pull Boxes, Ducts (this series includes remote signaling door bells, buzzers, annunciators) - Electrical	7506
Electrical Control-Panel Schedules - Electrical	7504
Electrical Control-Relay and Switch Schedules - Electrical.....	7507
Electrical Control-Timing Charts - Electrical.....	7503
Electrical Control-Wire Run Lists, Conduit, Cable and Wire Schedules - Electrical.....	7505
Electrical Control-Wiring Diagrams (elementary, connection and inter-connection) Block Diagrams - Electrical	7502
Electrical-General, Wiring Requirements -Electrical	7100
Electrical-Maps, Plot Plans, Plans and Profiles, Plans, Elevations, Sections, and Details (includes substation structures) - Electrical	8001
Electrical - Miscellaneous.....	9902
Electrical Only-Cable Schedules - Electrical.....	8005
Electrical Only-Pole Line Details, Sag Curves - Electrical	8003

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Electrical Only-Pole Schedules - Electrical	8004
Electrical Only-Transformer schedules (this series includes all electrical maps other than the "Civil" map series) - Electrical	8009
Electrical Only-Wiring Diagrams (elementary, connection and inter-connection) Area One-Line Diagram - Electrical	8002
Electrical-Outside Lines - Civil	0107
Electrical Utilities Transmission and Distribution Operating Drawings - Electrical	8000
Electronics-Drill and Trim - Electronics	6505
Electronics-General - Electronics	6500
Elevators - Mechanical	3901
Emergency Power-Generation Equipment (mechanical) - Mechanical	4050
Engineering Diagrams - Flow Diagrams	7001
Equipment Arrangements - Instrumentation	5907
Equipment Located in Hoods, Caves, Enclosure Where Operation is Remote - Mechanical	4705
Equipment Outline and Interface Requirement -	
Mechanical -	1575
Instrumentation -	5975
Electrical -	7575
Piping -	8575
Equipment Requirements - Instrumentation	5906
Equipment Support, Storage Racks, Hand Trucks, Tables, etc. - Mechanical	500306
Essential Drawings - Air (piping)	8606
Essential Drawings - Evacuation	0703
Essential Drawings - Fire Protection (piping)	8602
Essential Drawings - Fire Walls	0702
Essential Drawings - Gas (piping)	8604
Essential Drawings - Safety Showers/Eye Washes	8603
Essential Drawings - Simplified	0701
Essential Drawings - Steam (piping)	8605
Essential Drawings - Waste (piping)	8608
Essential Drawings - Water (piping)	8601
Essential Drawings - Vacuum (piping)	8607

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Excavation and Finishing Grading - Civil	0111
Experimental Test Facilities Excluding Fuel Specimens - Mechanical.....	2303
Extractors - Instrumentation	59—34
Extrusion Presses, Containers, Dies, and Tools - Mechanical	490222
Ex-Vessel Irradiated Fuel Handling Equipment - Mechanical	2452

- F -

Fences, Airport Runways, Roads, Walks, Parking Areas-Details and Profiles - Civil	0200
Fire Alarm and Telephone-Outside Lines - Civil	0108
Fire Alarm-Junction Pull Boxes, Ducts - Electrical	7706
Fire Alarm-Panel Schedules - Electrical	7704
Fire Alarm-Plans, Elevations, Sections and Details - Electrical	7701
Fire Alarm-Wire Run Lists, Conduit, Cable and Wire Schedules - Electrical.....	7705
Fire Alarm-Wiring Diagrams (elementary, connection, and inter-connection) Block Diagrams - Electrical	7702
Fire Protection, Fire Barrier Walls.....	1201
Fire Protection Sodium Systems - Mechanical	3000
Flow and Temperature Monitor Data Logging System - Instrumentation.....	59--40
Flow - Instrumentation.....	6002
Flux Monitor, System 95 - Instrumentation.....	59--78
Fuel Closed-Loop In-Reactor Assembly - Mechanical	4925
Fuel Driver Assembly - Mechanical	4922
Fuel Element Inspection-Radiography Inspection, Final Inspection Station, Weld Inspection, Length, Braze and Contour Inspection, Film Developing Equipment - Mechanical	490306
Fuel Element Production-Cleaning and Preparation - Mechanical.....	4901
Fuel Element Production-Component Salvage and Recover: Scrap Recovery - Mechanical.....	4904
Fuel Element Production-Component Salvage and Recover: Scrap Recovery - Mechanical.....	4905
Fuel Element Production-Component Supporting Facilities (not for new drawings) - Mechanical.....	4906
Fuel Element Production-Fuel Element Assembly Equipment - Mechanical.....	4902
Fuel Element Production-General - Mechanical.....	4900
Fuel Element Production-Special Items-Stampers, Tables, Bins Mechanical Counters - Mechanical	4907

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Fuel Element Production-Testing and Inspection - Mechanical	4903
Fuel Element Testing, Bond and Pen Tester, Autoclave Test, Bubble Tester - Mechanical	490308
Fuel Failure Monitoring, System 94 - Instrumentation	59--77
Fuel Handling-Irradiated (transfer, etc.) - Mechanical	2450
Fuel Material Open Test Assembly - Mechanical.....	4931
Fuel Monitor - Instrumentation.....	59--07
Fuel Oil Storage and Lines - Civil	0307
Fuel Open Test Assembly - Mechanical	4934
Fuel Special-Purpose Assembly - Mechanical.....	4929
Fuels Development - Mechanical	5003

- G -

Gas, Acids, Steam, Air Outside Lines - Civil	0308
Gas, Acids, Steam, Air, Overhead Lines-Piping - Civil	0300
Gas, Acids, Steam, Air Underground Lines - Civil	0306
Gas Seal Tools - Mechanical	2901
Gas Storage Tanks - Mechanical	2504
Gases and Water-Outside Lines - Civil.....	0104
General - Instrumentation	60--39
General-Maps - Civil	0109
Guard Vessel-Exterior Shields and other Cavity Components - Mechanical	1553

- H -

Heat Exchanger, Vessels, Columns, Tanks, Dissolves, (no moving parts) - Mechanical.....	2500
Heating and Ventilating Equipment Location - Heating, Venting, Exhaust.....	8901
Heating and Ventilating Schedules, Notes - Heating, Venting, Exhaust	8902
Helium Systems - Instrumentation.....	59--47
Hoods, Caves, Enclosures (remote operated equipment) - Mechanical.....	4700
Humidity - Instrumentation.....	6006

- I -

Impact Wrenches - Mechanical.....	4500
Indicator - Instrumentation	60--42

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Indicator Controller Alarm - Instrumentation.....	60--45
Indices - Electrical	7109
Instrument Engineering Diagrams - Flow Diagrams	7002
Instrument-Miscellaneous.....	9903
Instrumentation Aux. Liquid Metal, System SDD No. 81 - Instrumentation	59--57
Instrumentation Closed Loop, System SDD No. 61 - Instrumentation.....	59--56
Instrumentation-General, Index, Notes, Listings - Instrumentation.....	5900
Instrumentation Heat Transport, System SDD No. 51 - Instrumentation	59--55
Instrumentation Heating and Venting, System SDD No. 25 - Instrumentation.....	59--51
Instrumentation Impurity Monitoring and Analysis, System SDD No. 85 - Instrumentation	59--59
Instrumentation Inert Gas Receiving and Processing, System SDD No. 82 - Instrumentation	59--58
Instrumentation Plant Fire Protection, System SDD No. 25 - Instrumentation	59--52
Instrumentation Radioactive Waste, System SDD No. 24 - Instrumentation.....	59--50
Instrumentation Reactor, System SDD No. 31 - Instrumentation.....	59--54
Instrumentation Reactor Containment, System SDD No. 27 - Instrumentation	59--53
Instrumentation Reactor Plant Control, System SDD No. 90 - Instrumentation	59--60
Instrumentation Service Piping, System SDD No. 23 - Instrumentation.....	59--49
Instruments-General - Instrumentation	6000
Integrator - Instrumentation	60--46
Interface - Instrumentation.....	6017
Internal Structural Component Including Reactor Head - Mechanical.....	1551
Internals, Nonstructural Items Excluding Controls and Fuels Associated Equipment - Mechanical	1552
In-Vessel Fuel-Handling Equipment - Mechanical.....	2451

- J -

Junction Pull Boxes, Ducts - Electrical.....	7906
--	------

- K -

Key Area Maps - Civil.....	0101
----------------------------	------

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

- L -

Laboratory Apparatus - Mechanical	4800
Layout or Plot Plans-General Facility - Civil	0110
Level - Instrumentation.....	6003
Lighting-Junction Pull Boxes, Ducts - Electrical.....	7406
Lighting-Panel, Schedules - Electrical.....	7404
Lighting-Plans, Elevations, Sections, and Details - Electrical.....	7401
Lighting-Wire Run Lists, Conduit, Cable and Wire Schedules - Electrical	7405
Lighting-Wiring Diagrams (elementary, connections and inter-connections) - Electrical	7402
Logic Diagram - Flow Diagrams	7003

- M -

Machines and Equipment-Contaminated Zones - Mechanical	4750
Machines and Equipment (non-contaminated zones) Shop or General Purpose - Mechanical	2700
Machines, Mechanisms, and Dies for Forming, Fabricating or Assembling - Mechanical	500301
Machines-Process: Agitators, Pumps, Scales, Pulse Generators (moving parts) - Mechanical.....	2600
Machining, Forming, Including Tooling-Acme Gridley Cut-Off Lathes: Monarch Lathe - Mechanical.....	490210
Main Data-Logging System - Instrumentation	59--41
Manipulators - Mechanical	4702
Maps-Area Electrical Key - Civil	0102
Maps-Area Key - Civil.....	0101
Maps-Electrical, Plot Plans, Plans and Profiles, Plans, Elevations, Sections, and Details (includes substation structures) - Electrical	8001
Maps-General - Civil	0109
Maps-Project Key - Civil	0100
Material Handling Equipment-Conveyors, Pallets, Monorail Systems, Casks, Buckets - Mechanical.....	3902
Material Lists-General - Electrical.....	7108
Mechanical Equipment for Treatment of Water (other than piping) - Mechanical	4300
Mechanical - Miscellaneous	9901

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Mechanisms for Testing, Inspection, Calibration, etc - Mechanical.....	500302
Metal Solution Feed Preparation -Instrumentation	59--20
Metallurgical Test Materials, Destructive and Nondestructive - Mechanical.....	4727
Miscellaneous Equipment Pieces or Parts-Not Identifiable as Electrical, Instrument, or Mechanical Category; Unrelated to the Assembled Equipment - Miscellaneous	9900
Miscellaneous Survey Data-Columbia River Data, Civil Data - Civil	0501
Moderator-Graphite - Mechanical	1601
Moderator-Other than Graphite - Mechanical.....	1600
Moisture Detection - Instrumentation	59—45
Moisture - Instrumentation	6007
Motor Vehicles and Modifications - Mechanical	4101
- N -	
Nose and Cutoff Preparation - Mechanical.....	490114
- O -	
Off-Gas Treatment - Instrumentation	59--33
One-Line Diagrams - Electrical	7201
Open Test Assembly-Materials - Mechanical.....	4936
Open Test Assembly-Post Irradiation - Mechanical	4933
Open Test Assembly-Tooling - Mechanical	4935
Optical - Instrumentation	59--38
Optical Systems and Devices (including TV devices) - Mechanical	5000
Other Fuel Elements, as Cluster - Mechanical.....	490050
Other, Including Triple-Dip, Hot-Press, Heat-Treatment, Hydraulic-Press, Heavy-Duty Resistance Furnaces - Mechanical	490224
Other - Mechanical	490116
Outside Catch Tanks - Instrumentation	59—31
Outside Lines-Electrical - Civil	0107
Outside Lines-Sewers and Piping - Civil.....	0105
Outside Lines-Steam, Air, Gas, and Acids - Civil	0308

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Outside Lines-Telephone and Fire Alarm - Civil	0108
Outside Lines-Water and Gases - Civil.....	0104
Overhead and Underground Piping Composite - Civil.....	0305
Overhead Lines-Piping-Including Steam, Air, Gas, and Acids - Civil.....	0300
Overhead Piping Steam Condensate Air and Chemicals - Civil.....	0106

- P -

Panel Schedules - Electrical	7904
Panel Schedules, Wire Run Lists - Instrumentation.....	5902
Parking Area, Fences, Airport Runways, Roads, Walks-Details and Profiles - Civil.....	0200
Partition - Instrumentation	59--25
Penetration, Loader, Baskets - Mechanical.....	490108
Periscopes - Mechanical	5002
Personnel Radiation Monitor - Instrumentation.....	59--05
Pile Motion - Instrumentation.....	59--13
Piping-Acids and Chemicals - Piping	8503
Piping and Instrument Diagram CLS - Flow Diagrams	7005
Piping and Instrument Diagram - Flow Diagrams	7004
Piping and Mechanical Sections A1, 2, 3 - Piping	855301
Piping and Mechanical Sections B-2, 3, 4 - Piping	855302
Piping and Mechanical Sections C1-2, 3, 4, 5, 6, 7, 8, 9 - Piping.....	855303
Piping and Mechanical Sections D1, 2, 3, 4, 5, 6 - Piping	855304
Piping and Mechanical Sections E1, 2 - Piping	855305
Piping and Mechanical Sections F1, 2 - Piping	855306
Piping and Mechanical Sections G1, 2, 3 - Piping	855307
Piping and Mechanical Sections H1, 2, 3, 4, 5, 6, 7 - Piping.....	855308
Piping and Mechanical Sections J1, 2 - Piping.....	855309
Piping and Mechanical Sections K1, 2, 3, 4, 5, 6, 7 - Piping.....	855310
Piping and Mechanical Sections L1, 2, 3 - Piping	855311
Piping and Sewers-Outside Lines - Civil.....	0105

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Piping-Cell Arrangements (includes Diversion Boxes and Trenches) - Piping.....	8404
Piping-Compressed Air - Piping.....	8505
Piping-Cover Gas, Argon - Piping.....	8519
Piping-Demineralized and Distilled Water - Piping	8513
Piping-Drains and Waste Inside other-than Process - Piping	8509
Piping-Fire Extinguishing Gas, Vapor, Chemical or Powder - Piping	8515
Piping-Fuel Oil - Piping.....	8514
Piping-Gas Decay and Disposal - Piping.....	8504
Piping-Hangers, Support, Anchors, Guards - Piping	8511
Piping-Heating and Cooling Water - Piping.....	8516
Piping-Heating and Cooling NA and NAK, Insulating Requirements - Piping.....	8517
Piping-Heating and Cooling Gas - Piping.....	8518
Piping-Hydraulic - Piping.....	8512
Piping-Isometric - Piping.....	8548
Piping-Jumpers - Piping.....	8405
Piping-NA All Other - Piping.....	8554
Piping-NA Closed Loop - Piping.....	8553
Piping-NA Piping Components, Traps, Cold, Freeze and Vapor - Piping.....	8556
Piping-NA Receiving and Processing - Piping.....	8552
Piping-NA Reactor Secondary - Piping.....	8551
Piping NA Reactor Primary - Piping	8550
Piping-Process-All Others to Include: Buried or Exposed Inside Piping, Wash Down, Fog Spray, Solvent Blend, Slug Storage, Hot Shop, Utility Outlets Relative to Process Piping: Also Jets, Valves, Miscellaneous Process Piping - Piping.....	8407
Piping-Process-Operating or Sample Galleries - Piping	8406
Piping-Process Water-Foundation Cooling, Shielding, Horizontal Rods, Risers, and Cross Headers - Piping.....	8402
Piping-Process Water-Front or Rear Face - Piping	8401
Piping-Process Water - Piping	8400
Piping-Process Water-Valve Pits or Tunnels - Piping	8403

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Piping-Propane - Piping	8520
Piping-Radioactive Liquid Waste (water) - Piping	8409
Piping-Reference Drawings - Piping	8576
Piping-Refrigeration, Argon - Piping.....	8507
Piping-Service (includes Grouped Services, viz., Water, Air Steam Drains, etc.; Show on the Same Drawing) - Piping.....	8510
Piping-Special Loop - Piping.....	8555
Piping-Sprinkler Systems - Piping.....	8508
Piping-Steam-All Others - Piping	8502
Piping-Steam Radiators, Coils, and Condensate - Piping	8501
Piping-Vacuum - Piping	8506
Piping-Water Drains and Waste (non-contaminated) - Piping	8408
Piping-Water-Other than Process - Piping.....	8500
Plans, Elevations, Sections, and Details - Electrical	7901
Plans, Section, Elevations, and Details (including conduit and tubing) - Instrumentation.....	5901
Plant Protection, System 99 - Instrumentation.....	59--80
Plutonium Decontamination - Instrumentation.....	59--26
Plutonium Fuel Elements and related Components - Mechanical	490040
Poison Column and Associated Items - Mechanical	2250
Power-Electrical Equipment (motor, heaters, etc.) - Electrical	7308
Power-Ground Junction, Pull Boxes, Ducts, Raceways - Electrical.....	7306
Power House Equipment (associated with steam generation) - Mechanical	4000
Power-Lighting Protection - Electrical	7309
Power-Motor and Control Station Schedules - Electrical.....	7307
Power-Motor Control Centers, Switchgear, Transformers and Control Panels - Electrical	7303
Power-Panel Schedules - Electrical	7304
Power-Plans, Elevations, Sections, and Details (including grounding, block diagrams and engineering diagrams) - Electrical	7301
Power Plant Controls - Instrumentation	59--18

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Power-Wire Run Lists, Conduit, Cable, Wire Schedules - Electrical.....	7305
Power-Wiring Diagrams (elementary, connection and inter-connection) - Electrical.....	7302
Pre-cycle - Instrumentation.....	59--24
Pressure - Instrumentation	6004
Pressure Monitor - Instrumentation	59--08
Primary Elements - Instrumentation	60—49
Primary and Secondary Loop Instrumentation - Instrumentation	59--43
Process Flow Diagrams - Flow Diagrams.....	7000
Process Gas - Instrumentation	59--12
Process Monitoring and Control Annunciator, System 93-14 - Instrumentation.....	59--75
Process Monitoring and Control Aux. Liquid Metal, System 93-10 - Instrumentation.....	59--71
Process Monitoring and Control Closed Loop, System 93-3 - Instrumentation	59--65
Process Monitoring and Control Containment, System 93-1 - Instrumentation	59--63
Process Monitoring and Control Fire Protection, System 93-7 - Instrumentation.....	59--69
Process Monitoring and Control Heat Transport, System 93-2 - Instrumentation.....	59—64
Process Monitoring and Control Heating and Vent, System 93-6 - Instrumentation	59--68
Process Monitoring and Control Inert Gas Receiving and Process, System 93-8 - Instrumentation	59--70
Process Monitoring and Control Leak-Detection, System 93-13 - Instrumentation.....	59--74
Process Monitoring and Control Maintenance, System 93-12 - Instrumentation	59--73
Process Monitoring and Control Piping and Equipment Electrical Heating, System 93-15 - Instrumentation	59--76
Process Monitoring and Control Radioactive Waste, System 93-5 - Instrumentation.....	59--67
Process Monitoring and Control Refueling, System 93-11 - Instrumentation.....	59--72
Process Monitoring and Control Service Piping, System 93-4 - Instrumentation	59--66
Process Radiation Monitor - Instrumentation	59--04
Process Tubes - Mechanical.....	2200
Process Water - Instrumentation	59--11

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Process Water Monitor and Sampling - Instrumentation	59--10
Production of Power Reactor - Mechanical	1501
Products of Combustion Detectors - Instrumentation	59--48
Project Key Map - Civil	0100

- Q -

Quench Machines, Tanks, and Equipment - Mechanical	490208
--	--------

- R -

Radiation Dose Rates - Mechanical	1802
Radiation - Instrumentation	6014
Radiation Monitoring, System 96 - Instrumentation	59--79
Railroad Equipment and Rolling Stock Including Cask Car - Mechanical.....	4100
Railroad Structures and Details - Civil	0202
Railroads-Plans, Details, and Profiles - Civil	0201
Reactor and Vessel Instrumentation, System 92 - Instrumentation	59--62
Reactor Capsules-Metallurgical Tests - Mechanical	4706
Reactor Control Rod and Drive Mechanism - Mechanical	1504
Reactor Core Restraints - Mechanical	1506
Reactor Ex-Vessel Fuel Handling Equipment - Mechanical	1510
Reactor Fuel Transfer - Mechanical.....	1502
Reactor Gas Seal, Including Boots, Strips, etc. - Mechanical.....	2900
Reactor Inner Shield - Mechanical.....	1509
Reactor Instrument Tree and Drive Mechanism - Mechanical	1503
Reactor In-Vessel Handling and Drive Mechanism - Mechanical.....	1505
Reactor In-Vessel Storage Module - Mechanical	1507
Reactor Outer Shield - Mechanical.....	1508
Reactor Vessels-Arrangement Plans, Elevations., and Sections - Mechanical.....	1550
Recorder-Controller Alarm - Instrumentation	60--44

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Recorder - Instrumentation	60--40
Recovered Acid Storage - Instrumentation	59--28
Reflector Assembly - Mechanical.....	4937
Remotely Operated Connectors - Mechanical	4501
Roads, Walks, Parking Area, Fences, and Airport Runways, Details and Profiles - Civil.....	0200
Rock, Boring - Civil.....	0600
Rod Control System - Instrumentation	59--42
Rods Safety (SR) - Mechanical.....	1909
Rods Scram (CR) - Mechanical	1911
- S -	
Safety Circuits - Instrumentation	59--15
Samplers Process, Air, Stack Gas, etc. - Mechanical	4600
Schematic Diagrams - Instrumentation	5908
Scope - Miscellaneous	99--01
Seismoscope - Instrumentation	59--37
Self-Actuated Regulating Valve - Instrumentation	60--47
Sewer and Piping Outside Lines - Civil.....	0105
Sewer Lines-Process - Civil.....	0304
Sewer Lines-Sanitary - Civil.....	0303
Shielding-Biological - Mechanical	1800
Shielding-Thermal - Mechanical	1801
Shipping Containers-Boxes, Pallets - Mechanical	5010
Sleeve Preparation-Sleeve Cleaning Machine, Baskets - Mechanical.....	490108
Sodium Disposal Area Burial Grounds - Civil	0404
Sodium Processing Tanks - Mechanical	2505
Sodium Storage Tanks - Mechanical	2501
Sodium Systems - Instrumentation	59--39
Solvent Treatment - Instrumentation	59--22

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Sound - Instrumentation.....	6019
Special Tools - Miscellaneous	99--03
Special Tools, Wrenches, etc., - Mechanical	500303
Specific Gravity - Instrumentation.....	6012
Speed - Instrumentation	5009
Stack Sampling - Instrumentation.....	59--35
Steam, Air, Gas, and Acids Outside Lines - Civil	0308
Steam, Air, Gas, and Acids Overhead Lines Piping - Civil	0306
Steel Structural-Other Stop Logs, Underwater Doors, Trap Gates, Special Non-shield Doors, Allowable Floor Load Data - Architectural	1100
Steel Structural-Bench Marks and Control - Architectural.....	1101
Steel Structural-Penetrations - Architectural	1002
Steel Structural-Plans, Details, Schedules, Equipment Supports, Platforms - Architectural	1000
Steel Structural-Shop or Fabrication Drawings - Architectural	1001
Studies-General - Electrical	7107

- T -

Tank Farms - Instrumentation.....	59--32
Tanks, Dissolves, Heat Exchanger, Vessels, Columns (no moving parts) - Mechanical.....	2500
Telephone and Fire Alarm Outside Lines -Civil.....	0108
Temperature - Instrumentation General.....	6001
Temperature - Instrumentation System.....	59—09
Test Hole Facilities - Instrumentation.....	59--36
Test or Special-Purpose Reactor - Mechanical	1500
Testing Equipment-Destructive - Mechanical	4703
Testing Equipment, Nondestructive - Mechanical.....	4704
Third Safety System-Ball 3X - Mechanical.....	2100
Tools and Equipment for Decontamination - Mechanical	2204
Tools and Equipment for Horizontal Control Rods and Vertical Safety Rod Renovation - Mechanical.....	1903

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

Tools and Equipment for Over Boring Program - Mechanical.....	2205
Tools and Equipment for Process Tube Growth Correction - Mechanical.....	2202
Tools and Equipment Includes Tool Dolly - Mechanical	2201
Tools and Equipment Necessary to Operate Equipment in Hoods, Caves, and Enclosures - Mechanical.....	4701
Topography - Civil.....	0103
Transmitters - Instrumentation.....	60--48
Tubing Run List - Instrumentation.....	5905
- U -	
Underground and Overhead Piping-Composite - Civil	0305
Underground Lines, Steam, Air, Gas, and Acids - Civil	0306
Underground Process Water-Piping - Civil	0302
Underground Sanitary Water-Piping - Civil	0301
Underwater Monitor - Instrumentation	59--06
UNH Storage - Instrumentation	59--29
Uranium Decontamination - Instrumentation	59--27
- V -	
Vacuum Chambers and Component Parts and Equipment - Mechanical	500305
Vendor Information - Miscellaneous	99--02
Ventilation Controls - Instrumentation	59--17
Ventilation Exhaust and Heating System-Plans, Section, Details - Heating, Venting, Exhaust.....	8900
Vessels, Columns, Tanks, Dissolves, Heat Exchanger (no moving parts) - Mechanical.....	2500
Vibration - Instrumentation.....	6018
Viewing Windows and Ports - Mechanical.....	5001
Viscosity - Instrumentation.....	6010

**ATTACHMENT C – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
ALPHABETIC LISTING (cont.)**

- W -

Walks, Parking Areas, Fences, and Airport Runways, Roads-Details and Profiles - Civil	0200
Waste Disposal Systems-Sanitary: Septic Tanks, Tile Fields, Sewage Disposal Plant, Open Ditches, and Surface Drainage and Storm Drainage - Civil.....	0400
Waste Disposal Systems and Burial Grounds-Process: Dribs, Scavenging Impounding Areas, and Waste Facility Maps - Civil	0401
Waste Line Encasements -Diversion Boxes and Related Components - Civil	0403
Waste Storage-Tank Farms (including all drawings, except electrical and instrumentation and jumpers) - Civil	0402
Waste Storage-Tank Farms (including all drawings, except electrical and instrumentation and jumpers) - Civil	0405
Waste Storage Tanks, Contaminated Waste - Mechanical	2502
Waste Treatment - Instrumentation.....	59--23
Water and Gases Outside Lines - Civil.....	0104
Weight Factor - Instrumentation	6013
Weight - Instrumentation	6011
Welders Buffers and Controls, Controls, Vacuum Welders - Mechanical	490212
Wells, Well Fields-Irrigation Ditches and Water Supply - Civil.....	0500
Wire Run Lists, Conduit, Cable and Wire Schedules - Electrical.....	7905
Wiring Diagrams-Connections and Inter-Connections Elementary - Instrumentation	5903
Wiring Diagrams Elementary Connection and Inter-Connection Block Diagrams - Electrical	7902

- Z -

Zircaloy Component Preparation - Mechanical	490112
Zircaloy Uranium Fuel Elements, Billets, and Related Components-Cores, Copper or Zircaloy Components, End Caps or Plates, Brazing Rings, Self-Supports, Mixers, Perf, Dummies - Mechanical	490020

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING**

Civil

0000Drawing List
0100Project Key Map
0101Area Key Maps
0102Area Electrical Key Maps
0103Topography
0104Outside Lines-Water and Gases
0105Outside Lines-Sewers and Piping
0106Overhead Piping, Steam Condensate, Air and Chemicals
0107Outside Lines-Electrical
0108Outside Lines-Telephone and Fire Alarm
0209General Maps
0110Layout or Plot Plans-General Facility
0111Excavation and Finishing Grading
0200Roads, Walks, Parking Areas, Fences, and Airport Runways-Details and Profiles
0201Railroads-Plans, Details, and Profiles
0202Railroad Structures and Details
0300Overhead Lines-Piping-Including Steam, Air, Gas, and Acids
0301Underground Sanitary Water-Piping
0302Underground Process Water-Piping
0303Sewer Lines-Sanitary
0304Sewer Lines-Process
0305Composite of Overhead and Underground Piping
0306Underground Lines, Steam, Air, Gas, and Acids
0307Fuel Oil Storage and Lines
0308Outside Lines-Steam, Air, Gas, and Acids
0400Waste Disposal System-Sanitary: Septic Tanks, Tile Fields, Sewage Disposal Plant, Open Ditches, and Surface Drainage and Storm Drainage
0401Waste Disposal Systems and Burial Grounds-Process: Cribs, Scavenging Impounding Areas and Waste Facility Maps
0402Waste Storage-Tank Farms (including all drawings, except electrical and instrumentation and jumpers)
0403Waste Line Encasements-Diversion Boxes and Related Components
0404Sodium Disposal Area-Burial Grounds
0405Waste Storage Process Underground Tanks
0500Wells, Well Fields-Irrigation Ditches and Water Supply
0501Miscellaneous Survey Data-Columbia River Data, Civil Data
0600Rock Boring
0701Essential Drawings - Simplified
0702Essential Drawings - Fire Walls
0703Essential Drawings – Evacuation

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
 NUMERIC LISTING (cont.)**

Architectural and Structural

- 0800Architectural-Plans-May include other 0800 Category
- 0801Architectural-Elevations, Section and Details-Miscellaneous Steel for Stairs, Railing, etc
- 0802Architectural-Other (includes schedules, architectural equipment details, such as bins, signs, cabinets, laboratory equipment, etc.)
- 0803Architectural Doors-Shielding-Windows
- 0804Architectural-Equipment Locations
- 0900Concrete Structural-Plans
- 0901Concrete Structural-Elevations, Sections, and Details
- 0902Concrete Structural-Shop, Reinforcing and Pour Drawings
- 0903Concrete Structural-Penetrations, Sleeve and Block out
- 0904Concrete Structural-Penetrations Embedment Schedules
- 0905Concrete Structural-Demolition
- 1000Steel Structural-Plans, Details, Schedules, Equipment Supports, Platforms
- 1001Steel Structural-Shop or Fabrication Drawings
- 1002Steel Structural-Penetrations
- 1100Steel Structural-Other Stop Logs, Underwater Doors, Trap Gates, Special Non-shield Doors, Allowable Floor Load Data
- 1101Steel Structural-Bench Marks and Control
- 1201Fire Protection, Fire Barrier Walls

Mechanical

- 1500Test or Special Purpose Reactor
- 1501Production or Power Reactor
- 1502Reactor Fuel Transfer
- 1507Reactor In-Vessel Storage Model
- 1503Reactor Instrument Tree and Drive Mechanism
- 1504Reactor Control Rod and Drive Mechanism
- 1505Reactor In-Vessel Handling and Drive Mechanism
- 1506Reactor Core Restraints
- 1508Reactor Out Shield
- 1509Reactor Inner Shield
- 1510Reactor Ex-Vessel Fuel Handling Equipment
- 1550Reactor Vessels-Arrangements Plans, Elevations, and Sections
- 1551Internal Structural Component Including Reactor Head
- 1552Internals, Nonstructural Items Excluding Controls and Fuel Associated Equipment
- 1553Guard Vessel-Exterior Shields and Other Cavity Components
- 1575Equipment Outline and Interface Requirement
- 1600Moderator-Other than Graphite
- 1601Moderator-Graphite
- 1800Shielding-Biological
- 1801Shielding-Thermal
- 1802Radiation Dose Rates

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

- 1900Control Systems-Horizontal Rods
- 1901Control System-Vertical Rods
- 1902Control System-Poison
- 1903Tools and Equipment for Horizontal Control Rods and Vertical Safety Rods Renovation
- 1905Control Rods
- 1906Control Rods, Assembly Tooling and Handling Equipment
- 1907Control Rod, Absorber, Drive, Disconnect
- 1909Rods Safety (SR)
- 1911Rods Scram (CR)
- 2100Third Safety System-Ball 3X
- 2200Process Tubes (This covers all phases or process tubes from entry of water from common header to exit of water to common discharge header also tubes from point charging machine connects to the point that fuel is discharged.)
- 2201Tools and Equipment (necessary for installation or removal of process tubes and their associated parts. Includes tool dolly)
- 2202Tools and Equipment for Process Tube Growth Correction
- 2204Tools and Equipment for Decontamination
- 2205Tools and Equipment for Over Boring Program
- 2250Poison Column and Associated Items
- 2300All Test Equipment Where Operation of Pile is Essential to Operation of Test
- 2301All Facilities Build into Pile for Testing Purposes
- 2302Containers for Disposal of Contaminated Equipment (does not include metal handling buckets and shipping casks)
- 2303Experimental Test Facilities, Excluding Fuel Specimens
- 2400Charging Machines
- 2401Discharging and Manipulator for Rear Face Work
- 2450Fuel Handling-Irradiated (transfer, etc.)
- 2452Ex-Vessel Irradiated Fuel Handling Equipment
- 2451In-Vessel Fuel Handling Equipment
- 2500Vessels, Columns, Tanks, Dissolvers, Heat Exchangers (no moving parts)
- 2501Sodium Storage Tanks
- 2502Waste Storage Tanks (contaminated waste)
- 2504Gas Storage Tanks
- 2505Sodium Processing Tanks
- 2600Machines-Process: Agitators, Pumps, Scales, Pulse Generators (moving parts)
- 2700Machines and Equipment (non-contaminated zones) Shop or General Purpose
- 2800Cell Equipment Fastened to Cell for Mounting Vessels, Nozzles, Dunnage, Y Pads, etc.
- 2900Reactor Gas Seal, Including Boots Strips, etc.
- 2901Gas Seal Tools
- 3000Fire Protection Sodium Systems
- 3900Cranes (all types)
- 3901Elevators
- 3902Material Handling Equipment such as Conveyors, Pallets, Monorail Systems, Casks, Buckets
- 3903Crane Doors, Shielded, Non-Shielded
- 4000Power House Equipment (associated with steam generation)

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

4050Emergency Power Generation Equipment (mechanical)
4100Railroad Equipment and Rolling Stock (including cask car)
4101Motor Vehicles and Modifications
4300Mechanical Equipment for Treatment of Water (other than piping)
4500Impact Wrenches
4501Remotely Operated Connectors
4600Samplers (process, air, stack, gas, etc.)
4700Hoods, Caves, Enclosures (remotely operated equipment)
4701Tools and Equipment Necessary to Operate Equipment in Hoods, Caves, and Enclosures
4702Manipulators
4703Testing Equipment-Destructive
4704Testing Equipment-Nondestructive
4705Equipment Located in Hoods, Caves, Enclosure where Operation is Remote
4706Reactor Capsules-Metallurgical Tests
4727Metallurgical Test Materials, Destructive and
4750Machines and Equipment-Contaminated Zones
4800Laboratory Apparatus
4900Fuel Element Production-General
490010Aluminum Uranium Fuel Elements and Related Components-Caps, Spires, Cans, Sleeves,
Cores, Hollow Pieces, or Perfs, Dummies, Spaces, Wafers, Self-Supports
490020Zircaloy-Uranium Fuel Elements, Billets, and Related Components-Cores, Copper or Zircaloy
Components, End Caps or Plates, Brazing Rings, Self-Supports, Mixers, Perfs, Dummies
490030Ceramic Fuel Elements and Related Components
490040Plutonium Fuel Elements and Related Components
490050Other Fuel Elements, as Cluster
4901Fuel Element Production-Cleaning and Preparation
490102Core Preparation-Pickle Machine-Etch Machine, Nickel Plating
490104Aluminum Component Preparation-Caps and Can Cleaning Machine, Methanol Still, Detrex
Trichlor Still, Trays, Baskets, Racks
490106Sleeve Preparation-Sleeve Cleaning Machine, Baskets
490108Penetration, Loader, Baskets
490110Billet Core Preparation
490112Zircaloy Component Preparation
490114Nose and Cutoff Preparation
490116Other
490118Chemical Tanks and Piping
4902Fuel Element Production-Fuel Element Assembly Equipment
490202Duplex Furnace and Equipment-Ajax Induction Furnaces, Duplex Agitators, Agitator Baskets,
Loader Shields, Tools
490204Canning Furnace and Equipment-Canning Jacks, Canning Baskets, Tongs, Shields, Tools
490206Canning Cycle Control, Flex-O-Timer, Valves, etc
490208Quench Machines, Tanks, and Equipment
490210Machining, Forming, Including Tooling-Acme Gridley Cut-Off Lathes: Monarch Lathe
490212Welders, Buffers, Controls, Collets, and Vacuum Welders
490220Co-extrusion Component and Billet Assembly

ENGINEERING	Document	TFC-ENG-STD-10, REV A-8
	Page	67 of 98
DRAWING STANDARD	Issue Date	November 8, 2011

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

490222Extrusion Presses, Containers, Dies, and Tools

490224Other, Including Triple Dip, Hot Press, Heat Treatment, Hydraulic Press, Hevi-Duty
Resistance Furnaces

4903Fuel Element Production-Testing and Inspection

490302Component Mechanical Inspection-Pickle Inspection, Statistical Sampling, Recovered
Core Inspection, Gages

490304Component Electronic or Ultrasonic Testing-Transformation Test, Sort Tester, etc

490306Fuel Element Inspection-Radiography Inspection, Final Inspection Station, Weld Inspection,
Length, Braze and Contour Inspection, Film Developing Equipment

490308Fuel Element Testing, Bond and Pen Tester, Autoclave Test, Bubble Tester

4904Fuel Element Production-Component Salvage and Recover: Scrap Recovery

4905Fuel Element Production-Component Testing (not for new drawings)

4906Fuel Element Production-Component Supporting Facilities (not for new drawings)

4907Fuel Element Production-Special Items-Stampers; Tables; Bins; Mechanical Counters

4920Capsule Storage for Strontium

4921Capsule, Storage for Cesium

4922Fuel Driver Assembly

4925Fuel Closed-Loop In-Reactor Assembly

4928Fuel Special-Purpose Assembly

4931Fuel Material Open Test Assembly

4933Post-Irradiation Open Test Assembly

4934Fuel Open Test Assembly

4935Open Test Assemblies-Tooling

4936Materials Open Test Assembly

4937Reflector Assembly

5000Optical Systems and Devices (including TV devices)

5001Viewing Windows and Ports

5002Periscopes

5003Fuels Development

500301Machines, Mechanisms, and Dies for Forming, Fabricating, or Assembling

500302Mechanisms for Testing, Inspection, Calibration, etc

500303Special Tools, Wrenches, etc

500304Baskets, Tubes, Containers, and Component Parts

500305Vacuum Chambers and Component Parts and Equipment

500306Equipment Support, Storage Racks, Hand Trucks, Tables, etc.

5010Shipping Containers, Boxes, Pallets Conforming to DOT and RDT Regulations

Control Systems

5900Instrumentation-General, Index, Notes, Listings

5901Plans, Section, Elevations and Details (including conduit and tubing)

5902Panel Schedules, Wire Run Lists

5903Wiring Diagrams (connections and inter-connections), Elementary

5904Cable Schedules 5905 Tubing Run List

5906Equipment Requirements

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

5907Equipment Arrangements

5908Schematic Diagrams

Sub-Subject

04Process Radiation Monitor

05Personnel Radiation Monitor

06Underwater Monitor

07Fuel Monitor

08Pressure Monitor

09Temperature

10Process Water Monitor and Sampling

11Process Water

12Process Gas

13Pile Motion

14Calculator (Power)

15Safety Circuits

16Biological and Thermal Shield T/C System

17Ventilation Controls

18Power Plant Controls

19Dissolver Cells

20Metal Solution Feed Preparation

21Aqueous Make-Up

22Solvent Treatment

23Waste Treatment

24Pre-cycle

25Partition

26Plutonium Decontamination

27Uranium Decontamination

28Recovered Acid Storage

29UNH Storage

30Chemical Storage

31Outside Catch Tanks

32Tank Farms

33Off-Gas Treatment

34Extractors

35Stack Sampling

36Test Hole Facilities

37Seismoscope

38Optical

39Sodium Systems

40Flow and Temperature Monitor Data Logging System

41Main Data-Logging System

42Rod Control System

43Primary and Secondary Loop Instrumentation

44Control Room and Miscellaneous Instrumentation

45Moisture Detection

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

46.....	Argon Systems
47.....	Helium Systems
48.....	Products of Combustion Detectors
49.....	Instrumentation Service Piping, System SDD No. 23
50.....	Instrumentation Radioactive Waste, System SDD No. 24
51.....	Instrumentation Heating and Venting, System SDD No. 25
52.....	Instrumentation Plant Fire Protection, System SDD No. 26
53.....	Instrumentation Reactor Containment System SDD No. 27
54.....	Instrumentation Reactor, System SDD No. 31
55.....	Instrumentation Heat Transport System, SDD No. 51
56.....	Instrumentation Closed Loop, System SDD No. 61
57.....	Instrumentation Aux. Liquid Metal System, SDD No. 81
58.....	Instrumentation Inert Gas Receiving and Processing, System SDD No. 82
59.....	Instrumentation Impurity Monitoring and Analysis, System SDD No. 85
60.....	Instrumentation Reactor Plant Control, System SDD No. 90
61.....	Digital Data Handling and Display, System 91
62.....	Reactor and Vessel Instrumentation, System 92
63.....	Process Monitoring and Control Containment System 93-1
64.....	Process Monitoring and Control Heat Transport System 93-2
65.....	Process Monitoring and Control Closed Loop System 93-3
66.....	Process Monitoring and Control Service Piping, System 93-4
67.....	Process Monitoring and Control Radioactive Waste, System 93-5
68.....	Process Monitoring and Control Heating and Vent, System 93-6
69.....	Process Monitoring and Control Fire Protection System 93-7
70.....	Process Monitoring and Control Inert Gas Receiving and Processing, System 93-8
71.....	Process Monitoring and Control Aux. Liquid Metal, System 93-10
72.....	Process Monitoring and Control Refueling, System 93-11
73.....	Process Monitoring and Control Maintenance, System 93-12
74.....	Process Monitoring and Control Leak Detection, System 93-13
75.....	Process Monitoring and Control Annunciator, System 93-14
76.....	Process Monitoring and Control Piping and Equipment Electrical Heating, System 93-15
77.....	Fuel Failure Monitoring, System 94
78.....	Flux Monitor, System 95
79.....	Radiation Monitoring, System 96
80.....	Plant Protection, System 99
5975	Equipment Outline and Interface Requirement

Control Systems - General

6000	Instruments-General
6001	Temperature
6002	Flow
6003	Level
6004	Pressure
6005	Density

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

6006Humidity
6007Moisture
6008Conductivity
6009Speed
6010Viscosity
6011Weight
6012Specific Gravity
6013Weight Factor
6014Radiation
6015Differential Pressure
6016Acidity
6017Interface
6018Vibration
6019Sound
6020Component of a Mixture
Sub-Subject
39..... General
40..... Recorder
41..... Controller
42..... Indicator
43..... Alarm
44..... Recorder Controller Alarm
45..... Indicator Controller Alarm
46..... Integrator
47..... Self-Actuated Regulating Valve
48..... Transmitters
49..... Primary Elements
50..... Accelerator
51..... Alpha
52..... Amplifier
53..... Analyzer
54..... Calculator
55..... Calibrator
56..... Camera
57..... Chambers
58..... Checkers
59..... Counters
60..... Probes

Electronics - General

6500Electronics-General (wave type-includes radio, TV, microwave and laser)
6501Electronics-Plans, Elevations, Sections, and Details
6502Electronics-Wiring Diagrams (elementary, connection, and inter-connections)
6503Electronics-Transmitters Amplifiers, Receivers, and Control Consoles

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

6504Electronic-Wave Guides and Antennas

6505Electronic-Drill and Trim

Flow Diagrams

7000Process Flow Diagrams

7001Engineering Diagrams

7002Instrument Engineering Diagrams

7003Logic Diagrams

7004Piping and Instrument Diagram

7005Piping and Instrument Diagram CLS

Electrical

Numerical Subject Series: 73, 74, 75, 76, and 77 (Cover Inside Building - Electrical) 78 and 80 (Cover Outside Building - Electrical)

7100Electrical-General, Wiring Requirements (This series includes drawings of a composite nature. A drawing which shows a complete installation for a facility.)

7101Block Outs, Sleeves, Plans, and Details

7107Studies-General

7108Material Lists-General

7109Indices

7201One-Line Diagrams

7301Power-Plans, Elevations, Sections, and Details (including grounding, block diagrams, and engineering diagrams)

7302Power-Wiring Diagrams (elementary, connection, and inter-connection)

7303Power-Motor Control Centers, Switchgear, Transformers, and Control Panels

7304Power-Panel Schedules

7305Power-Wire Run Lists, Conduit, Cable, Wire Schedules, and Tray Schedules

7306Power-Grounding Junction, Pull Boxes, Ducts, Raceways

7307Power-Motor and Control Station Schedules

7308Power-Electrical Equipment (motors, heaters, etc.)

7309Power-Lighting Protection

7401Lighting-Plans, Elevations, Sections, and Details

7402Lighting-Wiring Diagrams (elementary, connections, and inter-connections)

7404Lighting-Panel, Schedules

7405Lighting-Wire Run Lists, Conduit, Cable and Wire Schedules

7406Lighting-Junction Pull Boxes, Ducts

7501Electrical Control-Control Panel Arrangements, Signal Plans, Elevations, Sections, and Details

7502Electrical Control-Wiring Diagrams (elementary, connection, and inter-connection) Block Diagrams

7503Electrical Control-Timing Charts

7504Electrical Control-Panel Schedules

7505Electrical Control-Wire Run Lists, Conduit, Cable and Wire Schedules

ENGINEERING	Document	TFC-ENG-STD-10, REV A-8
	Page	72 of 98
DRAWING STANDARD	Issue Date	November 8, 2011

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
 NUMERIC LISTING (cont.)**

- 7506Electrical Control-Junction Pull Boxes, Ducts (This series includes remote signaling door bells, buzzers, annunciators.)
- 7507Electrical Control-Relay and Switch Schedules
- 7508Electrical Control-Control Equipment and Devices
- 7575Equipment Outline and Interface Requirement
- 7601Communications-Plans, Elevations, Sections, and Details
- 7602Communications-Wiring Diagrams (elementary, connections, and inter-connection) Block Diagrams
- 7604Communications-Panel Schedules, Equipment, and Devices
- 7605Communications-Wire Run Lists, Conduit, Wire Schedules, Cables
- 7606Communication-Junction Pull Boxes, Ducts (This series includes sound-powered telephone and central station system telephones.)
- 7607Communications-Station Schedules
- 7701Fire Alarm-Plans, Elevations, Sections and Details
- 7702Fire Alarm-Wiring Diagrams (elementary, connection, and inter-connection) Block Diagrams
- 7704Fire Alarm-Panel Schedules
- 7705Fire Alarm-Wire Run Lists, Conduit, Cable and Wire Schedules
- 7706Fire Alarm-Junction Pull Boxes, Ducts
- 7801Cathodic Protection-Plans, Elevations, Sections and Details
- 7802Cathodic Protection-Wiring Diagrams (elementary, connection, and inter-connection) Block Diagrams
- 7806Cathodic Protection-Junction Pull Boxes, Ducts
- 7810Lighting Protection-Plans, Elevations, Sections and Details
- 7900Criticality Monitoring Systems
- 7901Plans, Elevations, Sections, and Details
- 7902Wiring Diagrams (elementary, connection, and inter-connection) Block Diagrams
- 7904Panel Schedules
- 7905Wire Run Lists, Conduit, Cable and Wire Schedules
- 7906Junction Pull Boxes, Ducts
- 8000Electrical Utilities Transmission and Distribution Operating Drawings (including switching diagrams and distribution maps)
- 8001Electrical-Maps, Plot Plans, Plans and Profiles, Plans, Elevations, Sections, and Details (includes substation structures)
- 8002Electrical Only-Wiring Diagrams (elementary, connection, and inter-connection) Area One-Line Diagram
- 8003Electrical Only-Pole Line Details, Sag Curves
- 8004Electrical Only-Pole Schedules
- 8005Electrical Only-Cable Schedules
- 8009Electrical Only-Transformer Schedules (This series includes all electrical maps other than the "Civil" map series.)

Insulation and Heat Tracing

- 8200Insulation and Heat-Tracing Reference Designs
- 8201Insulation and Heater Arrangements

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

8202Insulation Arrangements
8203Heater Applications-Piping
8204Heater Applications-Equipment
8205Heater Schedules
8206Insulation Schedules

Piping

8400Piping-Process Water
8401Piping-Process Water-Front or Rear Face
8402Piping-Process Water-Foundation Cooling, Shielding, Horizontal Rods, Risers, and Cross headers
8403Piping-Process Water-Valve Pits or Tunnels
8404Piping-Cell Arrangements (includes diversion boxes and trenches)
8405Piping-Jumpers
8406Piping-Process-Operating or Sample Galleries
8407Piping-Process-All other to include: Buried or Exposed Inside Piping, Wash Down, Fog Spray, Solvent Blend, Slug Storage, Hot Shop, Utility Outlets Relative to Process Piping: Also Jets, Valves, Miscellaneous Process Piping
8408Piping-Water Drain and Waste (non-contaminated)
8409Piping-Radioactive Liquid Waste (water)
8500Piping-Water-Other than Process
8501Piping-Steam Radiators, Coils, and Condensate
8502Piping-Steam-All Others
8503Piping-Acids and Chemicals
8504Piping-Gas Decay and Disposal
8505Piping-Compressed Air
8506Piping-Vacuum
8507Piping-Refrigeration, Argon
8508Piping-Sprinkler Systems
8509Piping-Drains and Waste Inside-Other than Process
8510Piping-Service (includes grouped services, viz., water, air, steam, drains, etc.; show on the same drawing)
8511Piping-Hangers, Support, Anchors, Guards
8512Piping-Hydraulic
8513Piping-Demineralized and Distilled Water
8514Piping-Fuel Oil
8515Piping-Fire Extinguishing Gas, Vapor, Chemical, or Powder
8516Piping-Heating and Cooling Water
8517Piping-Heating and Cooling NA and NAK, Insulating Requirements
8518Piping-Heating and Cooling Gas
8519Piping-Cover Gas, Argon
8520Piping-Propane
8548Piping-Isometric
8550Piping-NA Reactor Primary

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

8551Piping-NAK Reactor Secondary
8552Piping-NA Receiving and Processing
8553Piping-NA Closed Loop
855301Piping and Mechanical Sections A1, 2, 3
855302Piping and Mechanical Sections B1, 2, 3, 4
855303Piping and Mechanical Sections C1, 2, 3, 4, 5, 6, 7, 8, 9
855304Piping and Mechanical Sections D1, 2, 3, 4, 5, 6
855305Piping and Mechanical Sections E1, 2
855306Piping and Mechanical Sections F1, 2
855307Piping and Mechanical Sections G1, 2, 3
855308Piping and Mechanical Sections H1, 2, 3, 4, 5, 6, 7
855309Piping and Mechanical Sections J1, 2
855310Piping and Mechanical Sections K1, 2, 3, 4, 5, 6, 7
855311Piping and Mechanical Sections L1, 2, 3
8554Piping-NA all Other
8555Piping-Special Loop
8556Piping-NA Piping Components, Traps, Cold, Freeze, and Vapor
8557Piping-Equipment Outline and Interface Requirements
8576Piping-Reference Drawings
8601Essential Drawings - Water
8602Essential Drawings - Fire Protection
8603Essential Drawings - Safety Showers/Eye washes
8604Essential Drawings - Gas
8605Essential Drawings - Steam
8606Essential Drawings - Air
8607Essential Drawings - Vacuum
8608Essential Drawings - Waste

Heating, Venting, Exhaust

8900Ventilation Exhaust and Heating System-Plans, Section Details
8901Heating and Ventilating Equipment Location
8902Heating and Ventilating Schedules, Notes

Air Conditioning Systems

9000Air Conditioning Systems-Plans, Sections, Details

Miscellaneous

9900Miscellaneous Equipment Pieces or Parts-Not Identifiable as Electrical, Instrument or
Mechanical Category; Unrelated to the Assembled Equipment
9901Mechanical
9902Electrical
9903Instrument

**ATTACHMENT D – INDEX NUMBER SYSTEM FOR ENGINEERING DRAWINGS,
NUMERIC LISTING (cont.)**

Sub-Subject


01Scope

02 Vendor Information

03Special Tools


ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS

Figure E-1. General Symbology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-2. Civil Symbology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-3. Structural Symbology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-4. Architectural Symbolism Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-5. Mechanical/Machine Symbology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-8. Control Systems Symbolism Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-9. Electrical Symbolology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-10. Piping - P&Id Symbology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-11. Piping - Fittings Symbology Naming Standards.




ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-13. Piping - Jumper Components Symbology Naming Standards.



ATTACHMENT E – HANFORD DRAWING SYMBOLOGY STANDARDS (cont.)

Figure E-14. Piping - Jumper Details And Notes Symbology Naming Standards.



ATTACHMENT F – PARTS/MATERIALS LIST**A. Recommended Practices**

The following practices are industry proven and will assist in achieving the Parts/Materials List requirements listed in Section 3.22.

B. Arrangement

The Parts/Materials List should be arranged according to the following hierarchy:


1. Arrangement/installation or assembly
2. Subassemblies
3. Detailed items
4. Designed items
5. Commercial/catalog items
6. Hardware, e.g., bolts and nuts
7. Material items.

Three spaces should be provided between each category for future entries, see Example F-1. The sequence of items in the Parts/Materials List may be broken when items added by drawing development, progress, or revisions have used all reserved spaces.

C. Item Number/Find Number System

Items listed in the Parts/Materials List (assemblies, subassemblies, detailed items, commercial items, and material items) should be identified/located on the field of the drawing by item number as shown in Examples F-2 and F-3. Using this system allows the part number to be located in the Parts List and ensures that unique part numbering is maintained.

The item number is placed in a nominal 13 mm (.50") diameter circle with a radial leader pointing to the depicted item (see Figure F-1a).

Figure F-1. Part Call-Outs.**Figure F-1a.****Figure F-1b.**

ATTACHMENT F – PARTS/MATERIALS LIST (cont.)

Views detailing parts or assemblies should always have the item number centered below the primary view in a nominal 16 mm (.63”) circle. The nomenclature/description shown in the Parts List should always be used. The lettering height should be 6 mm (.24”) high and underlined (see Figure F-1b).

All associated items are to be located on the primary view where possible. Duplicate item number call-outs required for clarification may be used but held to a minimum and identified as reference call-outs by adding “REF” beside the circle.

D. Multiple Item Call-Outs

Where more than one item must be called out at one location, circled item numbers connected to one leader line may be stacked and quantities indicated as shown in Examples F-2 and F-3.

E. Items Not Requiring Pictorial Depiction

Items that do not require pictorial description for detail will be completely described, including dimensions, in the Parts/Materials List.


ATTACHMENT F – PARTS/MATERIALS LIST (cont.)

Example F-1. Parts/Materials List.

PARTS/MATERIAL LIST						
QTY	RECD	PART/DASH NUMBER	NOMENCLATURE/DESCRIPTION	MATERIAL/REFERENCE	SHT	ITEM NO
		-010	ASSEMBLY, GANTRY		1	1
		-020	SUBASSY, GRANTRY TRI-ASJUSTABLE		2	2
						3
						4
						5
1	3	-001	STABILIZER ROD	ASTM A36	2	6
	8	-002	HOLD DOWN CLAMP	ASTM A36	2	7
	1	-003	INSTRUMENT RACK	ASTM A36	2	8
	6	-004	MOUNTING BRACKET	ASTM A36	3	9
						10
						11
						12
	3	H-1-48149-020	SCAFFOLD ASSEMBLY			13
						14
						15
						16
	1	FR211-73	DUPLEX PUMP	MILTON ROY CO		17
	2	(SSS60TF8)	VALVE, BALL, 12 mm FNPT, CL 150	ASTM A275 (WHITNEY)		18
						19
						20
						21
						22
	4		SCREW, SCHD CAP, HEX M6X1-4g6gX50 mm L	ASTM A574M		23
AR	AR		TUBING, TS, 101.6 mm X 101.6 mm X 6.35 mm (4"X4"X.25")	ASTM A500, GR B		24
AR	AR		PLATE, 6.35 mm (.25") THK	ASTM A36		25
2	1		CONTINUOUS HINGE, BLANK, W/PIN 1.52 mm (.060") THK X 38.1 mm (1.50") WIDE X 1828.8 mm (72") LONG	TP 304 SST		26


ATTACHMENT F – PARTS/MATERIALS LIST (cont.)

Example F-2. Single/Stacked Item Call-Outs.



ATTACHMENT F – PARTS/MATERIALS LIST (cont.)

Example F-3. Single/Stacked Item Call-Outs.



ATTACHMENT F – PARTS/MATERIALS LIST (cont.)**F. Parts List Vertical Spacing**

To describe the part adequately, the Parts/Materials List vertical spacing may vary as required. Minimum spacing should not be less than 10 mm (.38”) as shown by Example F-1.

G. Applied Material

Applied material (see Attachment G, Glossary), when required for fabrication, assembly, or installation, should be identified in the General Notes with any required application instructions, unless covered by a separate specification.

H. Optional/Alternate Parts/Materials

The words “or equal” are not to be used for parts or material substitution on drawings. Optional or alternate materials may be provided for on engineering drawings in the following ways:

By referencing multiple brands/materials in the Parts List and/or in the field of the drawing, as applicable.

By specific instructions for optional or alternate items placed in the General Notes.

I. Quantity - Quantity Required Column

The quantities (number of items required) are always for one arrangement, one installation, or one assembly only.

J. Counted Quantities

Counted quantities are to be accurate and described in customary trade units.

K. As Required (AR)

Use AR only when an exact quantity is not known or cannot be easily predetermined (e.g., piping, structural steel shapes, tubing, shims, gasket material).

ATTACHMENT F – PARTS/MATERIALS LIST (cont.)

L. Identifying Assemblies

For ease in identifying assemblies, place an X in the quantity (QTY) column where the assembly is placed. The X can be used to quickly identify the items required for the assembly and to indicate that all the quantities in that column are for that assembly.

M. Reference Designation Column

This column should be used when unique identifiers are required. When used, the designator must correspond with the designator used in the field of the drawing. The width of the column is to be determined by the information required in the column (see Example F-4).

Example F-4. Parts/Materials List Example (Reference Designation).

PARTS/MATERIAL LIST							
QTY	RECD	REF DES	PART/DASH NUMBER	NOMENCLATURE/DESCRIPTION	MATERIAL/REFERENCE	SHT	ITEM NO
-020	-010			INSTALLATION			1
							2
1		SW-EV-CS-2	10250T1371	SWITCH, OPR, 3 POSN, SPR RTN FR RIGHT	CUTLER HAMMER		3
3		SW-P-X37 SW-P-X36-1 SW-P-X36-3	10250T20KB	SWITCH, SELECTOR, 2 POSN MAINTAINED, 1 NO-1 NC CONTACT OIL TIGHT	CUTLER HAMMER		4
7		DS-11,13,16,18, 19,20,21	10250T37R	INDICATING LIGHT, 120 VAC, XFMR TYPE WITH 6V LAMP & RED LENS, OIL TIGHT, PRESS TO TEST	CUTLER HAMMER		5
2		DS-12,14	10250T37G	INDICATING LIGHT, 120 VAC XFMR TYPE WITH 6V LAMP & GREEN LENS, OIL TIGHT, PRESS TO TEST	CUTLER HAMMER		6
1		BQ-C5	G0-405	TOTALIZER, DIGITAL, 110 VAC WITH EXTERNAL RECTIFIER	MOORE INDUSTRIES		7
1		PS2	111-24-125	POWER SUPPLY, 115 VAC/24 VDC, 125 WATT	RONAN		8
1		LELL-X37	4130-0X-601	PROBE, LEVEL ASSY WITH CABLE PROBE, WITH ENCLOSURE LENGTH: 145.5"	ENDRESS HAUSER		9

AR

ATTACHMENT F – PARTS/MATERIALS LIST (cont.)**N. Part/Dash Number Column**

See Section 4.22.4 and Attachment G, Glossary.

O. Vendor Part Number

Vendor part numbers are the manufacturer's part numbers (see Vendor [Supplier] Item in Attachment G, Glossary).

NOTE: The manufacturer's part number is to be used for commercial items. When only a distributor/vendor, e.g., McMaster Carr, Hanford Stores is known as a source, catalog numbers are noted as reference (in parentheses) in the Description Column or Material/Reference Column.

P. Nomenclature/Description Column

Enter the basic name (a noun name) first. The noun name is a noun or noun phrase that best establishes the basic concept of the item. It describes what the item is and what it is used for, not the material or method of fabrication. A compound noun or noun phrase is used only when a single noun is inadequate.

BASIC NAME EXAMPLE	
Bracket	(noun)
Piston	(noun)
Gear Box	(noun phrase)
Terminal Board	(noun phrase)

Use modifiers only when there is more than one type of the basic item used in the assembly (e.g., where two brackets are identified in an assembly, identified as bracket, mounting, and bracket, support).

Q. Description (Vendor [Supplier] Item)

Specify parts to obtain the most cost-effective item. Where possible, use generic descriptions rather than brand names. The description is to specify characteristics that are sufficient for intended end use, but still broad enough in definition to permit open purchasing.

ATTACHMENT F – PARTS/MATERIALS LIST (cont.)**R. Hardware and Material Items**

List basic names with required modifiers for fasteners and materials (e.g., SCH CAP SCR, ¼-20-UNC-2A, etc.). As required, list material items by form and size description (e.g., TUBE STEEL, 4 X 4 X ¼; PLATE, ½ THK).

S. Material/Reference Column

List the controlling specification for the required material (e.g., ASTM, ACI) followed by the kind of material (e.g., SST, 6061-T6A, CS). Never use the word “COMMERCIAL” to indicate any acceptable grade. The words “ANY GRADE” may be used where the grade of material is not a design factor. Always identify the specific material grade when welding is required. List names of supplier for commercial items, other separate documents controlling material, general notes, etc.

T. Sheet Column

For improved readability, always use this column to note where assemblies, arrangements, or detailed items are depicted on a multi-sheet drawing.

U. Item Number Column

Enter consecutive numbers starting with the numeral 1. An item number should always be used for each vertical space, including spaces left blank for future use.