REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 1

Please Direct Inquiries to:
ALICE R. HENDRICKSON

Title: PROC SPECIALIST
Phone: 509-376-9225

Authorized Signature

Alice Hendrickson Digitally signed by Alice Hendrickson
Date: 2015.11.23 07:05:55 -08'00'

Vendors Signature

RFQ Type: STANDARD RFQ

Quote Duration - **Days**
Payment Terms **%** **Days** **Net**

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0001	3	EA	**Catalog ID :** 0000674241 2	_____
	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #1, SY-FARM DUCTWORK,
BYPASS LINE WELDMENT, UPSTREAM, 4-IN.,
SCH. 10S,
STAINLESS STEEL, FABRICATE & TEST PER

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 2

DWG. H-14-110388, SHT. 1, ITEM 1; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 13, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS) AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2);

Manufacturer : UNKNOWN
Model :
Part : H-14-110388-010

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 4

B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0002	3	EA	**Catalog ID :** 0000674242 2	_____
	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #2, SY-FARM DUCTWORK, BYPASS LINE WELDMENT, DOWNSTREAM, 4-IN., 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110388, SHT. 1, ITEM 2; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 13, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED &

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110388-020

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 6

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0003	5	EA	**Catalog ID :** 0000674244 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #3 & #4, SY-FARM DUCTWORK, BYPASS LINE WELDMENT, ELBOW (LR), 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110388, SHT. 1, ITEMS 3 & 4; [NOTE: DWG. H-14-110388-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 8

WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)
NOTE: DWG. H-14-110388-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110388-030 & -040

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0004	1	EA	**Catalog ID :** 0000674247 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 9

Description: SPOOL, PIPE, #5, SY-FARM DUCTWORK, BYPASS LINE WELDMENT, ELBOW (LONG), 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110388, SHT. 1, ITEM 5; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 10

SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT (USE STAINLESS STEEL BANDING MATERIALS).

Manufacturer : UNKNOWN
Model :
Part : H-14-110388-050

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 11

B076 004 P Y PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079 005 P Y CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0005	7	EA	**Catalog ID :** 0000674249 2	_____
				_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #1, AN-FARM DUCTWORK, BYPASS LINE WELDMENT, UPSTREAM, 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110393, SHT. 1, ITEM 1; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 19, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 12

2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-010

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 13

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0006	7	EA	**Catalog ID :** 0000674250 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #2, AN-FARM DUCTWORK,
BYPASS LINE WELDMENT, DOWNSTREAM, 4-IN.,
SCH.,
10S, STAINLESS STEEL, FABRICATE & TEST
PER DWG. H-14-110393, SHT. 1, ITEM 2;
ALL MATERIAL REQUIRED FOR THIS
FABRICATION SHALL BE PROVIDED BY THE
FABRICATOR EXCEPT FOR ITEM 19, WHICH
WILL BE FURNISHED BY WRPS AS GOVERNMENT-
FURNISHED MATERIAL (GFM); VENDOR SHALL
PREPARE A DETAILED FABRICATION,
INSPECTION & TEST (FIT) PLAN (TRAVELER)
AND SUBMIT TO WRPS ENGINEERING & QA FOR

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 15

WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD
COVERS, DESIGNED TO KEEP THE INTERIOR OF
THE PIPING CLEAN AND PREVENT DAMAGE TO
FLANGE SEALING SURFACES, AND BE STRAPPED
TO STURDY WOODEN PALLETS FOR TRANSPORT.
(USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-020

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0007	9	EA	**Catalog ID :** 0000674251 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #3 & #4, AN-FARM DUCTWORK,
BYPASS LINE WELDMENT, ELBOW (LR), 4-IN.,
SCH. 10S, STAINLESS STEEL, FABRICATE &

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

TEST PER DWG. H-14-110393, SHT. 1, ITEMS 3 & 4; [NOTE: DWG. H-14-110393-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA,

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS) NOTE: DWG. H-14-110393-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-030 & -040

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 18

B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0008	1	EA	**Catalog ID :** 0000674253 2	_____
	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #5, AN-FARM DUCTWORK, BYPASS LINE WELDMENT, ELBOW (LONG), 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110393, SHT. 1, ITEM 5; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-050

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 20

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0009	2	EA	**Catalog ID :** 0000674254 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #6, AN-FARM DUCTWORK, BYPASS LINE WELDMENT, ELBOW (SR), 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110393, SHT. 1, ITEM 6; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 22

FLANGE SEALING SURFACES, AND BE STRAPPED
TO STURDY WOODEN PALLETS FOR TRANSPORT.
(USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-060

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0010	2	EA	**Catalog ID :** 0000674255 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #7, AN-FARM DUCTWORK,
BYPASS LINE WELDMENT, ELBOW (SR-LONG),
4-IN.,
SCH. 10S, STAINLESS STEEL, FABRICATE &
TEST PER DWG. H-14-110393, SHT. 1, ITEM
7; ALL MATERIAL REQUIRED FOR THIS

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 23

FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 24

CERTIFICATE OF CONFORMANCE (C OF C)
ATTESTING TO COMPLIANCE WITH THE
IDENTIFIED PURCHASE REQUIREMENTS
[QA CLAUSE B79] WITH THE COMPLETED
ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED
WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD
COVERS, DESIGNED TO KEEP THE INTERIOR OF
THE PIPING CLEAN AND PREVENT DAMAGE TO
FLANGE SEALING SURFACES, AND BE STRAPPED
TO STURDY WOODEN PALLETS FOR TRANSPORT.
(USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-070

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 25

0011 4 EA **Catalog ID :** 0000674256 2

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: WELDMENT, AN-FARM, INSTRUMENT STAND, PIPE, 2-IN., SCHEDULE 40S, STAINLESS STEEL
FABRICATE PER DWG. H-14-110393, SHT. 1, ITEM 8; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; CERTIFICATES OF CONFORMANCE (C OF C'S) TO THE REFERENCED STANDARD SHALL BE PROVIDED FOR ALL STRUCTURAL MATERIAL [QA CLAUSE B79]; STRUCTURAL WELDING & WELD INSPECTION SHALL BE PERFORMED IN ACCORDANCE WITH AWS D1.6-2007, STATICALLY LOADED CRITERIA. VT FINAL PASS FOR ALL WELDS. ALL WELD INSPECTIONS AND DIMENSIONAL VERIFICATION SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS (ITR'S) [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. INSTRUMENT STANDS SHALL BE

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 26

STRAPPED TO STURDY WOODEN PALLETS FOR
SHIPMENT. (USE STAINLESS STEEL BANDING
MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110393-080

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0012	8	EA	**Catalog ID :** 0000674257 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #1, AP-FARM DUCTWORK,
BYPASS LINE WELDMENT, UPSTREAM, 4-IN.,
SCH. 10S,
STAINLESS STEEL, FABRICATE & TEST PER
DWG. H-14-110398, SHT. 1, ITEM 1; ALL
MATERIAL REQUIRED FOR THIS FABRICATION
SHALL BE PROVIDED BY THE FABRICATOR

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

EXCEPT FOR ITEM 12, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 28

ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110398-010

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 29

0013 8 EA **Catalog ID :** 0000674302 2

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #2, AP-FARM DUCTWORK, BYPASS LINE WELDMENT, DOWNSTREAM, 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110398, SHT. 1, ITEM 2; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 12, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 30

= 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110398-020

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 31

B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0014	16	EA	**Catalog ID :** 0000674303 2	_____
_____	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #3 & #4, AP-FARM DUCTWORK, BYPASS LINE WELDMENT, ELBOW (LR), 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110398, SHT. 1, ITEMS 3 & 4; [NOTE: DWG. H-14-110398-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS &

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS) NOTE: DWG. H-14-110398-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 33

THE DRAWING CALLS IT OUT AS GENERAL
SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110398-030 & -040

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0015	6	EA	**Catalog ID :** 0000674304 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #1, AW-FARM DUCTWORK,
BYPASS LINE WELDMENT, UPSTREAM, 4-IN.,
SCH. 10S,
STAINLESS STEEL, FABRICATE & TEST PER
DWG. H-14-110403, SHT. 1, ITEM 1; ALL
MATERIAL REQUIRED FOR THIS FABRICATION
SHALL BE PROVIDED BY THE FABRICATOR

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 34

EXCEPT FOR ITEM 14, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 35

ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110403-010

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 36

0016 6 EA **Catalog ID :** 0000674305 2

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #2, AW-FARM DUCTWORK, BYPASS LINE WELDMENT, DOWNSTREAM, 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110403, SHT. 1, ITEM 2; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 14, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

= 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110403-020

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0017	12	EA	**Catalog ID :** 0000674306 2	_____
	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #3 & #4, AW-FARM DUCTWORK, BYPASS LINE WELDMENT, ELBOW (LR), 4-IN., SCH. 10S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110403, SHT. 1, ITEMS 3 & 4; [NOTE: DWG. H-14-110403-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS &

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS) NOTE: DWG. H-14-110403-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 40

THE DRAWING CALLS IT OUT AS GENERAL
SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110403-030 & -040

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0018	4	EA	**Catalog ID :** 0000674308 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: STAND, INSTRUMENT, AW-FARM, WELDMENT,
PIPE, 2-IN., SCHEDULE 40S, STAINLESS
STEEL, FABRICATE PER DWG. H-14-110403,
SHT. 1, ITEM 5; ALL MATERIAL REQUIRED
FOR THIS FABRICATION SHALL BE PROVIDED
BY THE FABRICATOR; VENDOR SHALL PREPARE
A DETAILED FABRICATION, INSPECTION &

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 41

TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; CERTIFICATES OF CONFORMANCE (C OF C'S) TO THE REFERENCED STANDARD SHALL BE PROVIDED FOR ALL STRUCTURAL MATERIAL [QA CLAUSE B79]; STRUCTURAL WELDING & WELD INSPECTION SHALL BE PERFORMED IN ACCORDANCE WITH AWS D1.6-2007, STATICALLY LOADED CRITERIA. VT FINAL PASS FOR ALL WELDS. ALL WELD INSPECTIONS AND DIMENSIONAL VERIFICATION SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS (ITR'S) [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. INSTRUMENT STANDS SHALL BE STRAPPED TO STURDY WOODEN PALLETS FOR SHIPMENT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110403-050

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac Standard Name Rev S/P Text Line Terms and Conditions - Text at End

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 42

B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0019	2	EA	**Catalog ID :** 0000674309 2	_____
				_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #1, AY-FARM DUCTWORK, BYPASS LINE WELDMENT, UPSTREAM, 4-IN., SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110408, SHT. 1, ITEM 1; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 15, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 44

Manufacturer : UNKNOWN
Model :
Part : H-14-110408-010

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0020	2	EA	**Catalog ID :** 0000674310 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #2, AY-FARM DUCTWORK, BYPASS LINE WELDMENT, DOWNSTREAM, 4-IN., SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110408, SHT. 1, ITEM 2; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 15, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 46

THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110408-020

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0021	2	EA	**Catalog ID :** 0000674311 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 47

Description: SPOOL, PIPE, #3, AY-FARM DUCTWORK, BYPASS LINE WELDMENT, HORIZ. CONNECTION, 4-IN., SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110408, SHT. 1, ITEM 3; [NOTE: DWG. H-14-110408-030 (ITEM 3) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS) NOTE: DWG. H-14-110408-030 (ITEM 3) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110408-030

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac Standard Name Rev S/P Text Line Terms and Conditions - Text at End

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 49

B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0022	2	EA	**Catalog ID :** 0000674314 2	_____
	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #4, AY-FARM DUCTWORK, BYPASS LINE WELDMENT, VERTICAL CONNECTION, 4-IN. SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110408, SHT. 1, ITEM 4; [NOTE: DWG. H-14-110408-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 51

TO STURDY WOODEN PALLETS FOR TRANSPORT.
(USE STAINLESS STEEL BANDING MATERIALS)
NOTE: DWG. H-14-110408-040 (ITEM 4)
SHALL BE FABRICATED SS/QL-2 EVEN THOUGH
THE DRAWING CALLS IT OUT AS GENERAL
SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110408-040

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0023	2	EA	**Catalog ID :** 0000674318 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #1, AZ-FARM DUCTWORK,
BYPASS LINE WELDMENT, UPSTREAM, 4-IN.,
SCH. 40S,

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110535, SHT. 1, ITEM 1; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 15, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 53

USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110535-010

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 54

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0024	2	EA	**Catalog ID :** 0000674319 2	_____
				_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #2, AZ-FARM DUCTWORK, BYPASS LINE WELDMENT, DOWNSTREAM, 4-IN., SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110535, SHT. 1, ITEM 2; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR EXCEPT FOR ITEM 15, WHICH WILL BE FURNISHED BY WRPS AS GOVERNMENT-FURNISHED MATERIAL (GFM); VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 55

ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS)

Manufacturer : UNKNOWN
Model :
Part : H-14-110535-020

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac Standard Name Rev S/P Text Line Terms and Conditions - Text at End

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 56

B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0025	2	EA	**Catalog ID :** 0000674321 2	_____
	_____	__		_____

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #3, AZ-FARM DUCTWORK, BYPASS LINE WELDMENT, HORIZ. CONNECTION, 4-IN., SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110535, SHT. 1, ITEM 3; [NOTE: DWG. H-14-110535-030 (ITEM 3) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 58

TO STURDY WOODEN PALLETS FOR TRANSPORT.
(USE STAINLESS STEEL BANDING MATERIALS)
NOTE: DWG. H-14-110535-030 (ITEM 3)
SHALL BE FABRICATED SS/QL-2 EVEN THOUGH
THE DRAWING CALLS IT OUT AS GENERAL
SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110535-030

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)
	B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
	B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
	B052	000	P	Y	INSPECTION AND TEST REPORT
	B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
	B079	005	P	Y	CERTIFICATE OF CONFORMANCE

Line	*Quantity*	*UP*	*Item Description*	*Unit Price*
0026	2	EA	**Catalog ID :** 0000674330 2	

Need Date : 02/01/2016 **Destination** RICHLAND WA

Description: SPOOL, PIPE, #4, AY-FARM DUCTWORK,
BYPASS LINE WELDMENT, VERTICAL
CONNECTION,

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

4-IN., SCH. 40S, STAINLESS STEEL, FABRICATE & TEST PER DWG. H-14-110535, SHT. 1, ITEM 4; [NOTE: DWG. H-14-110535-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE]; ALL MATERIAL REQUIRED FOR THIS FABRICATION SHALL BE PROVIDED BY THE FABRICATOR; VENDOR SHALL PREPARE A DETAILED FABRICATION, INSPECTION & TEST (FIT) PLAN (TRAVELER) AND SUBMIT TO WRPS ENGINEERING & QA FOR APPROVAL AND INSERTION OF WITNESS AND/OR HOLD POINTS [QA CLAUSE B13]; AT A MINIMUM, THE TRAVELER SHALL CONTAIN A HOLD POINT FOR WRPS VERIFICATION OF DRAWING DIIMENSIONS PRIOR TO THE START OF FABRICATION. (SEE DRAWING GENERAL NOTE 2); CERTIFIED MATERIAL TEST REPORTS (CMTR'S) SHALL BE SUPPLIED FOR ALL PIPING, PIPE FITTINGS & WELD FILLER MATERIAL [QA CLAUSE B49]; DUCTWORK PIPING SHALL BE FABRICATED, INSPECTED & TESTED IN ACCORDANCE WITH ASME B31.3-2012 FOR CATEGORY NORMAL FLUID SERVICE. VT THE FINAL PASS FOR ALL WELDS. VENDOR SHALL PERFORM A PNEUMATIC PRESSURE TEST ON EACH COMPLETED PIPE SPOOL PER ASME B31.3, PARAGRAPH 345.5 AND DOCUMENT THE RESULTS ON A TEST REPORT. (TEST PRESSURE = 1.25 X 150 PSIG (DESIGN) = 187.5 (+2/-0) PSIG). ALL WELD INSPECTIONS, DIMENSIONAL VERIFICATION AND PRESSURE TESTING SHALL BE DOCUMENTED ON INSPECTION & TEST REPORTS, WHICH SHALL INCLUDE THE INSPECTION/TEST

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST

PROCEDURE USED, RESULTANT DATA, TRACEABILITY TO THE ITEM INSPECTED OR TESTED AND AN AUTHORIZED SIGNATURE. [QA CLAUSE B52]; VENDOR SHALL SUBMIT SUSPECT/COUNTERFEIT ITEM (S/CI) DOCUMENTATION [QA CLAUSE B76] AND A CERTIFICATE OF CONFORMANCE (C OF C) ATTESTING TO COMPLIANCE WITH THE IDENTIFIED PURCHASE REQUIREMENTS [QA CLAUSE B79] WITH THE COMPLETED ASSEMBLIES. PIPE SPOOLS SHALL BE FITTED WITH TEMPORARY CLOSURES, SUCH AS PLYWOOD COVERS, DESIGNED TO KEEP THE INTERIOR OF THE PIPING CLEAN AND PREVENT DAMAGE TO FLANGE SEALING SURFACES, AND BE STRAPPED TO STURDY WOODEN PALLETS FOR TRANSPORT. (USE STAINLESS STEEL BANDING MATERIALS) NOTE: DWG. H-14-110535-040 (ITEM 4) SHALL BE FABRICATED SS/QL-2 EVEN THOUGH THE DRAWING CALLS IT OUT AS GENERAL SERVICE.

Manufacturer : UNKNOWN
Model :
Part : H-14-110535-040

Lead Time Days	Method of Shipment	FOB	FOB Point

Fac	Standard Name	Rev	S/P	Text	Line Terms and Conditions - Text at End
	B001	001	P	Y	QA PROGRAM SUBMITTAL AND PRE-AWARD SURVEY
	B004	000	P	Y	SUPPLIER QUALITY PROGRAM EVALUATION
	B013	001	P	Y	FABRICATION/INSPECTION/TEST PLAN (TRAVELER)
	B025	000	P	Y	CERTIFIED WELD INSPECTOR (CWI)

REQUEST FOR QUOTATION

THIS IS NOT AN ORDER!

Return RFQ Response to:
WASHINGTON RIVER PROTECTION
SOLUTIONS, LLC
PO BOX 850 MSIN H6-16
RICHLAND WA 99352

RFQ Number : 00040197
Issue Date : 11/23/2015
Due Date : 12/15/2015
Due Time : 12:00 PST
Page : 61

B028	001	P	Y	WELDING PROCEDURES AND QUALIFICATIONS
B049	002	P	Y	CERTIFIED MATERIAL TEST REPORT
B052	000	P	Y	INSPECTION AND TEST REPORT
B076	004	P	Y	PRCMT OF POTENTIALLY SUSPECT OR COUNTERFEIT ITEMS
B079	005	P	Y	CERTIFICATE OF CONFORMANCE

1.0 Solicitation

1.1 North American Industry Classification System (NAICS) Code and Size Standard

The authorized procurement representative has determined that North American Industry Classification System (NAICS) Code 332996 applies to this acquisition. Therefore, the size standard for determining whether an Offeror is a small business in regard to this solicitation is 500 employees. The small business size standard for a concern which submits an offer in its own name, other than on a construction or service contract, but which proposes to furnish a product which it did not itself manufacture, is five hundred (500) employees.

1.2 Representations and Certifications

Washington River Protection Solutions, LLC (WRPS) requires the electronic submission of the Representations and Certifications through its vendor registration web site (www.hanford.gov/chgcp). To start the submission, the Offeror will need to be registered with WRPS and have obtained a vendor identification number and form number (password). If assistance is required, please contact WRPS Contract Support at the following email address WRPS_Procurement@rl.gov.

For this solicitation, an Offeror is required to have an electronic Representations and Certifications on file with WRPS for the North American Standard Coding System (NAICS) code identified in this document. The certification for this specific NAICS code will be valid for twelve (12) months from its submission unless your firm's business conditions change and an updated Representations and Certification submission is then required to be submitted electronically.

1.3 Facsimile/Telephone Proposals

To meet this solicitation's due date, your proposal may be submitted by telephone, email or facsimile. If any of these methods are utilized to submit the offeror's proposal, a written confirmation will be provided to the authorized procurement representative.

To send a facsimile or email, address the facsimile to the authorized procurement representative and include a solicitation number or Subcontract/Purchase Order number for reference along with the specific information requested in the solicitation.

The authorized procurement representative's contact information is:

Email Address: Alice_R_Hendrickson@rl.gov
Phone Number: 509-376-9225
Fax Number: 509-376-0825

1.4 Delivery Date Evaluation

Delivery by the desired delivery date will be a principal consideration in evaluating Proposals. The authorized procurement representative will evaluate these Proposals on the basis of which best serves the interest of WRPS and the Department of Energy.

DELIVERY DATES:

SY FARM 04/25/2016

AP, AN & AW FARMS 08/17/2016

AY & AZ FARMS 09/22/2016

1.5 Evaluation of Discount

Discounts for early payment will be considered during the solicitation's evaluation. The minimum number of days that will be considered during the solicitation's evaluation shall be ten (10) days. Discount periods will be computed from the receipt of a correct invoice or receipt of merchandise, whichever is later, to the date of WRPS's payment date. Unless freight and/or other charges are itemized, the discount will be applied to the full invoice amount.

1.6 Proposal Submittal

1. Proposals are to be received by the close of business (4:00 P.M., PST) on the date specified in the Solicitation.
2. Other Proposal Methods

   Proposals, upon approval by the authorized procurement representative, may be submitted by electronic mail, telephone, or facsimile. When requested, the original proposal and certifications shall be sent to the authorized procurement representative as confirmation.
3. Late Proposals

   Any proposal received at the office designated in the solicitation after the exact time specified for receipt will not be considered unless it is received before award is made, and:

   a. It was sent by registered or certified mail not later than the fifth calendar day prior to the date specified for receipt of offers (e.g., an offer submitted in response to a solicitation requiring receipt of offers by the 20th of the month must have been mailed by the 15th or earlier); or

   b. It was sent by mail, telephone, telegram or facsimile as specified by the authorized procurement representative and it is determined that the late receipt was due solely to mishandling upon receipt; or

   c. It is the only proposal received.
4. Proposal Changes

Any modification of a proposal, including a modification resulting from the authorized procurement representative's request for a "best and final offer" is subject to the same conditions as in the "Late Proposals" section above.

5. Withdrawal of Proposals

   Proposals may be withdrawn by written or electronic notice received at any time prior to award. An Offeror or its authorized representative may withdraw proposals in person, provided its identity is made known and he signs a receipt for the proposal prior to award.

1.7 Financial Capability Determination

WRPS reserves the right, prior to award, to request any or all Offerors to submit data which will be used to make a determination of financial capability to perform on any resultant Subcontract. Such data may include, however not be limited to, current annual reports, lines of credit with financial institutions and suppliers, and/or any other such data as may be required to make a determination of the Offerors' financial capabilities.

1.8 Buy American Act Compliance

The provisions of this solicitation include each of the Federal Acquisition Regulation (FAR) clauses that may be applicable to the Offeror's proposal, as well as any resulting purchase order or Subcontract. The applicability of a specific FAR clause is based on the proposed dollar amount of your proposal for the supplies or materials provided under a purchase order or Subcontract unless the item is classified as a commercial off the shelf (COTS) item, and in turn, does not apply.

The applicable FAR clauses in the provisions and the corresponding clause for which identification may be required are shown below:

FAR Clause in Subcontract Provisions	**Corresponding FAR Clause Requiring Offeror Certification**
FAR 52.225-1, "Buy American Act—Supplies" (Jun 2003)	FAR 52.225-2, "Buy American Act Certificate" (Jun 2003)
FAR 52.225-3, "Buy American Act—Free Trade Agreements—Israeli Trade Act"(Jan 2004)	FAR 52.225-4, "Buy American Act—Free Trade Agreements—Israeli Trade Act Certificate" (Jan 2005) Alternate I - applies if the quote for an end item or supplies under a time-and-materials subcontract is $25,000 or more but less than $50,000. Alternate II - applies if the quote for an end item or supplies under a time-and-materials subcontract is $50,000 or more but less than $58,550.

FAR 52.225-5, "Trade Agreements" (Jan 2005)	FAR 52.225-6, "Trade Agreements Certificate" (Jan 2005)

1.9 Employment Eligibility Verification (E-Verify)

WRPS anticipates that this award will be subject to the Employment Eligibility Verification requirements established in Federal Acquisition Regulations (FAR) clause 52.222-54.which requires the successful Offeror to enroll and utilize the E-Verify program. Enrollment is done via the Internet at the Department of Homeland Security Web site at http://www.dhs.gov/E-Verify. This requirement is applicable to all awards that are more than $3,000 and not considered a commercial item as defined in FAR Part 2.101.

WRPS reserves the right, prior to award, to require Offeror to submit information which WRPS will use to make a determination whether Offeror has successfully enrolled in the E-Verify program. Such information may include a copy of the last three (3) pages of the enrollment form (i.e. pages 11, 12, and 13) and any other information that may be required to make the appropriate determination.

2.0 QA/Inspection Requirements

2.1 Quality Assurance Program Submittal and Pre-Award Survey

(B01) 5/8/07

The Offeror shall submit the quality assurance program manual that addresses the quality assurance programs identified herein. The formal submittal documentation (cover letter) shall identify the specific bid request and project.

If the Offeror's manual has been previously approved by the Buyer but is not current, the manual shall be updated and resubmitted to the Buyer with the proposal. If the manual has not changed since its previous approval by the Buyer, a statement to this effect shall be submitted with the proposal. The Buyer shall evaluate the Offeror's Quality Assurance program prior to contract award. This evaluation may include a survey of quality program implementation at the Offeror's facilities. If a program change is required, it will be identified to the Offeror prior to contract award. A deficient or inadequate program may be used as the basis to deny award of this contract.

2.2 Supplier Quality Program Evaluation

(B04) Rev. 0 02/22/00

The Supplier shall document, implement, and maintain a quality assurance program which is consistent with applicable criteria as noted in the attached WRPS QUALITY ASSURANCE REQUIREMENTS document dated 11/02/2015. The Supplier's program is subject to review at

all times by the Buyer. The Supplier's program, written for compliance with a quality assurance program standard other than the one imposed on the Purchase Order/Contract Order, may be acceptable if it complies with the quality assurance program requirements specified.

When subcontracting any portion of this Purchase Order/Contract Order, the Supplier is required to invoke the applicable quality assurance program requirements on the subcontractor.

The Buyer reserves the right to verify the quality of work at the Supplier's facility, including any subcontractor's facility. Access to a subcontractor's facility shall be requested through the Supplier and verification may be performed jointly with the Supplier.

The Supplier shall, during the performance of this Purchase Order/Contract Order, submit proposed changes to the quality assurance program to the Buyer for review prior to implementation.

Fabrication/Inspection/Test Plan (B13) Rev. 0 2/22/00

Fabrication/Inspection/Test Plan (Traveler)

The Supplier shall prepare a detailed fabrication/inspection/test plan (Traveler) for insertion of Buyer-designated source inspection/witness notification points. Prior to starting work, the plan shall be submitted to the Buyer for review, approval and insertion of Buyer's designated inspection/witness notification points unless otherwise specified in procurement documents. The plan shall include the following:

1. Traceability to Buyer's Purchase Order/ Contract Order document number.
2. Description of items to be fabricated/tested/inspected (e.g., components, subassemblies, assemblies).
3. Sequential fabrication/process steps.
4. Sequential points for inspection and tests to be performed during fabrication/processing.
5. Method/procedure to be used for performance of inspection/test/fabrication, including:
    a. Each characteristic or attribute to be evaluated,
    b. The report form to be utilized,
    c. Specific Codes/Standard requirements as specified by procurement documents i.e., ASME, ASTM, ANSI, etc., and
    d. Sampling plans for final characteristics (e.g., AQL, lot size, inspection level), where applicable.

Subsequent revisions/modifications to the fabrication/inspection/test plan document require review and approval by the Buyer prior to implementation of the change. When subcontracting any portion of this Purchase Order/Contract Order, the Supplier is required to invoke the applicable quality assurance program requirements on the subcontractor.

2.3 Certified Weld Inspector (CWI)

(B25) Rev. 0 02/9/00

Supplier personnel performing weld inspections shall be certified as a Certified Weld Inspector (CWI) in accordance with the requirements specified in AWS QC-1.

The following documentation shall be submitted prior to the start of fabrication:

1. Current AWS CWI certificates.
2. Current and valid visual acuity examination. The examination must be performed annually.
3. Visual weld inspection procedures.

Approval shall be obtained from the Buyer prior to start of fabrication.

2.4 Welding Procedures and Qualifications

(B28) Rev. 1 12/03/02

Welding procedures and personnel shall be qualified in accordance with the applicable AWS or ASME specifications as specified in the Purchase Order/Contract order. The Supplier shall submit copies of all welding procedures, Procedure Qualification Records, and Welder Qualification Records to be employed in the performance of this Purchase Order/Contract Order. Buyer approval is required prior to the start of fabrication.

Changes and revisions to welding documentation shall be submitted to the Buyer for review and approval prior to use. When subcontracting any portion of this Purchase Order/Contract Order, the Supplier is required to invoke the applicable quality assurance program requirements on the subcontractor.

2.5 Certified Material Test Report

(B49) Rev. 2 03/17/06

The Certified Material Test Report (CMTR) shall include actual results of all chemical analysis, tests, examinations, and treatments required by the material specification and this Purchase Order/Contract order. The CMTR shall be legible, reference applicable specification number and year of edition, and be traceable to the material furnished by heat or lot number. All reports are subject to review and acceptance by the Buyer.

One copy of the documentation, unless otherwise specified, shall accompany the applicable item(s) shipped.

2.6 Inspection and Test Report

(B52) Rev. 0 02/22/00

The Supplier shall submit legible, reproducible copies of Inspection/Test Reports.

The report(s) shall include the following:

1. Identification of the applicable inspection and/or test procedure utilized.
2. Resulting data for all characteristics evaluated, as required by the governing inspection/test procedure.
3. Traceability to the item inspected/tested, (i.e., serial number, part number, lot number, etc.).
4. Signature of the Supplier's authorized representative or agency which performed the inspections/tests.

One copy of the documentation, unless otherwise specified, shall accompany the applicable item(s) shipped.

2.7 Procurement of Potentially Suspect or Counterfeit Items

(B76) Rev. 2 02/25/08

Notwithstanding any other provisions of this agreement, the Supplier warrants that all items provided to the Contractor shall be genuine, new and unused unless otherwise specified in writing by the Contractor. Supplier further warrants that all items used by the Supplier during the performance of work for the Hanford Site, include all genuine, original, and new components, or are otherwise suitable for the intended purpose. Furthermore, the Supplier shall indemnify the Contractor, its agents, and third parties for any financial loss, injury, or property damage resulting directly or indirectly from material, components, or parts that are not genuine, original, and unused, or not otherwise suitable for the intended purpose. This includes, but is not limited to, materials that are defective, suspect, or counterfeit; materials that have been provided under false pretenses; and materials or items that are materially altered, damaged, deteriorated, degraded, or result in product failure.

Types of material, parts, and components known to have been misrepresented include (but are not limited to) fasteners; hoisting, shackles, turnbuckles, cable clamps, wire rope, rigging, and lifting equipment; cranes; hoists; valves; pipe and fittings; electrical equipment and devices; plate, bar, shapes, channel members, and other heat treated materials and structural items; welding rod and electrodes; and computer memory modules. The Supplier's warranty also extends to labels and/or trademarks or logos affixed, or designed to be affixed, to items supplied or delivered to the Contractor. In addition, because falsification of information or documentation may constitute criminal conduct, the Contractor may reject and retain such information or items, at no cost, and identify, segregate, and report such information or activities to cognizant Department of Energy officials.

Supplier shall provide a written statement that "all items furnished under this Purchase Order/Contract Order are genuine (I.e., not counterfeit) and match the quality, test reports, markings and/or fitness for use required by the Purchase Order/Contract Order.

The statement shall be on supplier letterhead and signed by an authorized agent of the supplier.

Any materials furnished as part of this Purchase Order/Contract Order which have been previously found to be suspect/counterfeit by the Department of Energy shall not be accepted.

For further information on suspect/counterfeit items, reference the Department of Energy (DOE) Guide DOE G 414.1-3

DOE Guide web address,

http://www.directives.doe.gov/pdfs/doe/doetext/neword/414/g4141-3.pdf

2.8 Certificate of Conformance

(B79) Rev. 4 12/2/2009

The Supplier shall provide a legible/reproducible Certification of Conformance. Supplier's authorized representative responsible for quality shall sign the Certification of Conformance.

This Certification of Conformance shall, as a minimum:

1. Identify the appropriate Purchase Order/Contract Order number under which the material, equipment, item or service is being supplied.
2. Each Order/shipment shall include a C of C unique to that shipment.
3. The quantity of each Line Item shipped shall be identified on the C of C.
4. The COC shall identify the specific procurement requirements to be met by the purchased item or service. The procurement requirements identified shall include any approved changes, waivers, or deviations applicable to the item or service.
5. For OCRWM-related items only, the COC shall also identify any procurement document requirements that have not been met together with an explanation and the means for resolving the nonconformances.
6. The COC shall be signed or otherwise authenticated by a supplier's representative. For Quality Level 1 & 2 and OCRWM-related items, the person signing the COC shall be the one who is responsible for this QA function and whose responsibilities and position are described in the supplier's QA program.

One copy of the documentation, unless otherwise specified, shall accompany the applicable item shipped. For subsequent shipments on this Purchase Order/Contract order, reference may be made to documentation provided with earlier shipments, instead of duplicating such documentation.

3.0 Packaging and Marking

3.1 Biodegradable/Recyclable Packaging Materials

It is the preference of WRPS that the SUBCONTRACTOR packages the material/equipment in biodegradable or recyclable packaging materials. Cardboard and/or paper containers, in place of plastic, shall be used whenever possible and practical. Paper and/or popcorn may be used for internal container protection instead of plastics, foam or polyurethane chips. This preference is not intended to transfer any liability to WRPS for damage during shipping or prior to receipt by WRPS. The SUBCONTRACTOR shall be solely responsible for determining whether such

substitution is practical, safe for its intended use, or in violation of any commercial or manufacturer's warranty that WRPS may otherwise receive. Although this preference is not a prerequisite for award of this Subcontract, the SUBCONTRACTOR's packaging methods may become a consideration for future awards.

4.0 Transportation/Receiving Instructions

4.1 FOB Designation

Responses are invited on both a FOB Origin and FOB Destination basis. Offerors will be evaluated for award (either FOB Origin or FOB Destination) based on the lowest overall price to WRPS. Please complete the information below and include the total charges as applicable to meet the solicitation's requirements.

FOB Origin: Insert the exact shipping location, weights, and dimensions for each item or shipping lots. Include an explanation of any special factors that could affect loading, shipping or handling.

FOB Destination: Delivery to WRPS's address as specified with all transportation charges paid by the Offeror. The total price shown on the Offeror's proposal is an all-inclusive firm fixed price.

5.0 Contract Administration

5.1 Document Transmittals – Master Submittal Register (MSR)

The SUBCONTRACTOR shall utilize the BUYER's document transmittal system for the exchange of data and information during the performance of Work under this Subcontract. Master Submittal Register (MSR) Form A-6005-317 is included as an attachment to the Subcontract and identifies the required SUBCONTRACTOR submittals. SUBCONTRACTOR information shall be transmitted using TOC Incoming Letter of Transmittal (form A-6005-315) to the address indicated therein.

Submittals may be transmitted electronically to TOCVND@rl.gov or a BUYER designated File Transfer Protocol (FTP) site. For electronic transmittals, all transmittal subject headings shall contain, at a minimum, the subcontract number, submittal number, and submittal description.

5.2 Price-Anderson Amendments Act (PAAA)

The Subcontractor shall comply with the Article entitled Price-Anderson Amendments Act (PAAA) contained in the General Provisions and shall have a process in place to ensure compliance with the applicable Nuclear Safety Rules.

5.3 Contractor Employee Whistleblower Rights and Requirement To Inform Employees of Whistleblower Rights (FAR 52.203-17)

(a) This contract and employees working on this contract will be subject to the whistleblower rights and remedies in the pilot program on Contractor employee whistleblower protections established at 41 U.S.C. 4712 by section 828 of the National Defense Authorization Act for Fiscal Year 2013 (Pub. L. 112-239) and FAR 3.908.

(b) The Subcontractor shall inform its employees in writing, in the predominant languet of the workforce, of employee whistleblower rights and protections under 41 U.S.C. 4712, as described in section 3.908 of the Federal Acquisition Regulation.

(c) The Subcontractor shall insert the substance of this clause, including this paragraph (c), in all subcontracts over the simplified acquisition threshold.

5.4 Conditions and Risks of Work

The SUBCONTRACTOR represents that it has carefully examined the drawings and specifications for the Work and has fully acquainted itself with all other conditions relevant to the Work and the SUBCONTRACTOR assumes the risk of such conditions and will, regardless of such conditions, the expense, difficulty of performing the Work, or negligence, if any, of the BUYER, fully complete the Work for the stated Subcontract price without further recourse to BUYER.

6.0 List of Attachments

The following attachments are incorporated herein. The General Provisions and On-Site Work Provisions, if applicable, listed below are hereby incorporated into and made a part of this Subcontract. They shall have the same force and effect as if written into the body of the contract. Subcontractor is responsible for downloading and complying with the applicable revision as identified below.

The documents identified with an asterisk below can be downloaded from the following website: http://www.hanford.gov/tocpmm/page.cfm?page=11

Title	Revision	Date
* General Provisions	3	06-21-2011
*Firm Fixed Price Contract Type	2	10-31-2012
Master Submittal Register (MSR), A-6005-317	MR-15-05732	
Incoming Letter of Transmittal, A-6005-315	2	
Request for Information (RFI), A-6003-417	7	
RFI Instructions		
H-14-110388 SHT 1	0	09-21-2015
H-14-110388 SHT 2	0	09-21-2015
H-14-110393 SHT 1	0	09-26-2015
H-14-110393 SHT 2	0	09-26-2015
H-14-110393 SHT 3	0	09-26-2015
H-14-110398 SHT 1	0	09-26-2015
H-14-110398 SHT 2	0	09-26-2015
H-14-110403 SHT 1	0	09/25-2015

H-14-110403 SHT 2	0	09-25-2015
H-14-110408 SHT 1	0	09-25-2015
H-14-110408 SHT 2	0	09-25-2015
H-14-110408 SHT 3	0	09-25-2015
H-14-110535 SHT 1	0	09-26-2015
H-14-110535 SHT 2	0	09-26-2015
H-14-110535 SHT 3	0	09-26-2015
QUALITY ASSURANCE REQUIREMENTS	0	11/02/2015