


Tank Waste Remediation System

Chapter 3



Tank Farm Operations

How Big is the “Tank Farm Machine?”

- 28 double-shell tanks
- 149 single-shell tanks
- 40 inactive miscellaneous underground storage tanks
- 8 active miscellaneous underground storage tanks
- ~200 miles of underground pipe
- ~50,000 valves
- ~1,400 intertank transfer lines
- 22 active ventilation systems

Ongoing Tank Farm Activities

- Routine
 - 54,000 radiation zone entries per year to:
 - Perform ~4,000 equipment preventative maintenance items per year
 - Perform ~2,000 equipment repairs/year
 - Make ~100 waste transfers per year from other cleanup efforts (~500,000 gallons received in 1997)
 - Read over 8,000 active instruments each year to ensure environmental and worker safety
 - Take over 13,000 radiological data points each year to ensure environmental and worker safety

Ongoing Tank Farm Activities (cont'd)



- Major
 - Interim Stabilization (saltwell pumping)
 - 119 of 149 tanks complete
 - Start pumping one additional tank in FY 1998
 - Tank 101-SY mixer pump operation continues
 - Slight rise in surface level being investigated
 - Surface area decontamination
 - 7.5 million square feet out of 8.8 million square feet completed;
1.25 million square feet in FY 1997
 - Rebaselining of vadose zone contamination using new spectral gamma measurement technology


New Projects:

Cross-Site Transfer System



New, environmentally compliant transfer line between 200 West and 200 East Areas

- RCRA Compliant System
- Pipe-within-a-pipe design (~6.2 miles long)
- Capable of transferring liquids and sludges
- Operational in Summer 1998




New Projects:

AY/AZ Tank Farm Ventilation System



- Operational in March 1998
- Provides upgrades to ventilation for aging double-shell waste tanks
 - Filtration systems
 - Closed loop cooling system
 - Continuous stack monitoring and sampling system (compliant system)
 - Automated leak detection and gas absorption capability
- Eliminates liquid discharges to the environment
 - Double-encased underground piping with leak monitoring




New Projects: Project W-314

Tank Farm Restoration and Safe Operations

- Phase I provides upgrades to the waste transfer system to support safe, reliable waste feed to the private contractors
 - Double-contained waste transfer lines
 - Instrument/control and electrical upgrades
 - Pit modifications
- Phase II provides plant modifications to:
 - Improve infrastructure reliability
 - Reduce operations and maintenance costs

FY 1998 Operations Budget



Problem:

Tank Leakage to the Vadose Zone

- 67 single-shell tanks have leaked in the past
 - About 1 million gallons (2 percent of current tank waste volume)
 - About 1 million curies (0.5 percent of total tank radioactivity)
- By comparison, 450 billion gallons (0.1 million curies) were discharged to the soil via cribs, ponds and ditches in the 200 Areas, with some discharges adjacent to tanks.
- In 1997, DOE confirmed that prior tank leakage had impacted groundwater.
- Some radionuclides are moving faster and deeper into the vadose zone than previously estimated

Vadose Zone Contamination - What is being done?



- Evaluating the use of surface controls to slow or stop liquid from seeping into the ground
- Characterizing the lower vadose zone (from the bottom of the tank to the groundwater)
- Completing the spectral gamma logging baseline for presence of radionuclides beneath the 200 Areas
- Independent reviews of activities and programs
- Integrating data needs with the Environmental Restoration Groundwater Monitoring program
- Compiling historical monitoring and soil characterization data
- Working with Tribal Nations and Regulators to finalize a TWRS Vadose Zone Characterization Program Plan

Problem: Delays Associated with Interim Stabilization



- 119 of 149 single-shell tanks have been interim stabilized (pumpable liquids have been removed).
- Three formerly leaking tanks are scheduled to start pumping.
 - Restart one tank in FY 1998
 - Initiate pumping on two tanks in FY 2000
- New starts are limited by system constraints (for example, transfer lines, tank capacities, etc.)
- Pathforward to complete saltwell pumping in FY 2004 has been implemented
 - Recovery Plan submitted to the Washington State Department of Ecology

Tank Farm Operations - Points of Contact

- Dana C. Bryson - Director
Waste Storage Division
– (509) 372-0738
- Michael J. Royack - Operations Manager
Waste Storage Division
– (509) 376-4420
- Thomas R. Hoertkorn - Projects Manager
Waste Storage Division
– (509) 376-7412